# AYLESBURY ESTATE REGENERATION

# **TOTAL ESTATE COST REVIEW**

Date: 6<sup>th</sup> May 2005

Frost Associates Hill House MacDonald Road Highgate Hill London N19 5NA

Telephone: 020 7281 5777 Facsimile: 020 7281 5778

E-mail: rec@frostassociates.co.uk

Signed .	
	Michael J. Dodd M.R.I.C.S., M.A.S.I.
Data	

### 1. Executive Summary

A review of the total cost of the Aylesbury Estate has been carried out based on the data contained in the BPTW Report issued today.

The review has considered both the refurbishment and strengthening of the entire estate to Decent Homes and Decent Homes+ standards and the New Build of housing and the Day Care centre in the South West Corner.

The programme of works is anticipated to extend into the year 2011, which means that it will not be possible for all of the estate to meet the Decent Homes standard by the end of 2010.

The results of the review are as follows:


Estimated Cost of Refurbishing the whole estate to Decent Homes Standard	£261,420,000
Estimated Cost of Refurbishing the whole estate to Decent Homes+ Standard	£354,540,000
Estimated Cost of New Build Housing and Day Care	£ 33,940,000
Estimate Cost of Strengthening as part of the Decent Homes Standard (Construction works plus Design Fees only)	£ 14,900,000
Estimate Cost of Strengthening as part of the Decent Homes+ Standard (Construction works plus Design Fees only)	£ 9,760,000

A detailed build up of the estimated costs is given in the Appendix to this review.

## 2. Basis of Calculations and Assumptions

- 2.1. The Programme of works has been set at 6 years commencing in May 2006.
- 2.2. The rate of inflation has been set at 6% per annum.
- 2.3. No allowances have been made for dealing with ground contamination, diversion of services, legal fees or Section 106 matters.
- 2.4. Decant Cost during the strengthening operation have been calculated as £150 per dwelling per day for 4 weeks.
- 2.5. Decant Storage and Removal has been calculated as a total of £1,000 per dwelling.
- 2.6. Decant Subsistence has been calculated at £500 per dwelling.
- 2.7. Loss of Rent has been calculated at £75 per dwelling for 4 weeks.
- 2.8. Compensation to decanted Leaseholders has been calculated at £1,500 per dwelling.
- 2.9. Compensation to Leaseholders who are not decanted for strengthening works has been calculated at £500 per dwelling.
- 2.10. An allowance of  $\mathfrak{L}750$  per dwelling has been allowed for creating party wall agreements and monitoring them.
- 2.11. An additional contingency of £5,000,000 for the CHP, over and above the estimate used in BPTW's Decent Homes+ scheme, has been included to allow for the highest pricing level predicted by the consultant, Orchard Partners London Ltd.





# TOTAL COST REVIEW OF AYLESBURY ESTATE

for

SBDS

6th May 2005

SUMMARY OF CONSTRUCTION COSTS TO REFURBISHED PROPERTIES		Decent Homes	Decent Homes + $\mathfrak{L}$	•
SOUTH WEST CORNER PHASE 1A		19,510,000	29,090,000	
SOUTHWEST CORNER PHASE 1B		18,500,000	23,620,000	
REMAINDER OF THE ESTATE		153,310,000	203,100,000	
TOTAL ESTIMATE AT 1ST QUARTER 2005 PRICES	•	191,320,000	255,810,000	
GENERAL CONTINGENCY	10%	19,130,000	25,580,000	
SPECIAL CONTINGENCY ON CHP ESTIMATE		0	5,000,000	
INFLATION 1st Qtr 2005 to 4th Qtr 2011	6%	47,610,000	64,790,000	
ESTIMATE OF CONSTRUCTION WORKS	,	258,060,000	351,180,000	
OTHER SOFT COSTS TO BE CONSIDERED		£	£	
DECANT COSTS DURING STRENGTHENING	315	1,320,000	1,320,000	
DECANT STORAGE AND REMOVAL COSTS	315	320,000	320,000	
DECANT SUBSISTANCE ALLOWANCE	315	160,000	160,000	
LOSS OF RENT DURING STRENGTHENING DECANT	315	90,000	90,000	
COMPENSATION TO DECANTED LEASEHOLDERS	120	180,000	180,000	
COMPENSATION TO OTHER LEASEHOLDERS	350	180,000	180,000	
PARTY WALL MATTERS	315	240,000	240,000	
GENERAL CONTINGENCY	10%	250,000	250,000	
INFLATION 1st Qtr 2005 to 4th Qtr 2011	6%	620,000	620,000	
ESTIMATE OF SOFT COSTS	į	3,360,000	3,360,000	
ESTIMATE OF TOTAL ESTATE REFURBISHMENT WO	ORKS	£261,420,000	£354,540,000	
SOUTH WEST CORNER NEW BUILD		£	£	
DWELLINGS ON DAY CARE SITE	76 UNITS	12,310,000	12,310,000	
DWELLINGS ON BOYSON ROAD SITE	31 UNITS	5,160,000	5,160,000	
DWELLINGS ON CHARTRIDGE RD INFILL SITES	25 UNITS	3,930,000	3,930,000	
NEW DAY CENTRE	25 ON110	3,760,000	3,760,000	
GENERAL CONTINGENCY	10%	2,520,000	2,520,000	
INFLATION 1st Qtr 2005 to 4th Qtr 2011	6%	6,260,000	6,260,000	
5 514 131 Qui 2000 10 Aut Qui 2011	5/6	0,200,000	0,200,000	
ESTIMATE OF NEW BUILD		£33,940,000	£33,940,000	
ESTIMATE OF REFURBISHMENT AND NEW BUILD C	OSTS	£295,360,000	£388,480,000	

### SUMMARY BY PHASE AND BUILDING

	De	ecent Homes			Decent Homes -	+
	Construction	Soft Costs	Total (£)	Construction	Soft Costs	Total (£)
PHASE 1A						
42-256 Bradenham	9,199,147	1,640,570	10,839,717	14,058,791	2,155,424	16,214,215
1-172 Chiltern	7,550,521	1,121,631	8,672,152	11,380,283	1,491,853	12,872,137
PHASE 1B						
1-68 Chartridge	4,141,759	581,482	4,723,241	5,315,813	696,803	6,012,616
69-76 Chartridge	443,493	90,531	534,024	622,523	109,606	732,129
77-105 Chartridge	1,038,173	162,585	1,200,758	1,696,762	232,065	1,928,827
106-119 Chartridge	1,019,192	167,694	1,186,886	1,259,595	191,562	1,451,157
120-149 Chartridge 1-41 Bradenham	1,117,824 2,289,039	172,366 631,158	1,290,190 2,920,197	1,796,196 3,044,226	243,946 706,672	2,040,142 3,750,899
1-28 Arklow	798,146	144,016	942,162	1,490,446	215,969	1,706,416
1-12 Red Lion	421,084	68,587	489,671	689,270	96,834	786,104
External Works	4,316,941	624,969	4,941,910	4,316,941	624,969	4,941,910
Drainage	253,568 32,588,888	20,032 5,425,622	273,600 38,014,510	253,568 45,924,415	20,032 6,785,736	273,600 52,710,151
	02,000,000	0,420,022	30,014,310	40,024,410	0,700,700	32,710,131
REMAINDER OF THE ESTAT						
1-240 Wendover	12,914,122	1,903,851	14,817,972	18,298,392	2,501,690	20,800,082
241-471 Wendover 1-215 Taplow	12,429,842 11,568,901	1,398,575 1,523,671	13,828,418 13,092,571	17,612,202 16,392,310	1,974,330 2,059,073	19,586,532 18,451,383
76-165 Missenden	4,842,796	741,154	5,583,949	6,861,897	2,059,073 965,724	7,827,621
166-255 Missenden	4,842,796	625,893	5,468,689	6,861,897	850,125	7,712,022
1-61 Gayhurst	4,733,137	632,563	5,365,701	5,786,187	655,015	6,441,202
62-79 Gayhurst	1,131,641	211,340	1,342,981	1,535,026	256,150	1,791,176
80-144 Gayhurst 145-162 Gayhurst	4,086,483 1,348,431	538,373 240,697	4,624,856 1,589,128	5,543,151 1,676,029	700,377 275,143	6,243,528 1,951,172
1-20 Hambleton	1,257,379	225,177	1,482,556	1,705,585	275,154	1,980,739
1-31 Calverton	1,948,938	301,789	2,250,727	2,643,656	379,000	3,022,656
1-31 Danesfield	1,948,938	301,789	2,250,727	2,643,656	379,000	3,022,656
1-18 Gaitskell 19-42 Gaitskell	1,078,519	206,630 247,022	1,285,149	1,481,904	251,440	1,733,344
43-66 Gaitskell	1,438,025 1,438,025	247,022	1,685,047 1,685,047	1,975,872 1,975,872	306,657 306,657	2,282,528 2,282,528
1-35 Emberton	2,200,414	329,801	2,530,215	2,984,773	416,670	3,401,443
1-30 Foxcote	1,797,532	287,076	2,084,608	2,469,840	361,873	2,831,713
1-81 Ravenstone	5,990,517	756,850	6,747,367	7,491,772	915,945	8,407,717
1-61 Latimer 62-85 Latimer	4,887,987 1,787,585	653,388 290,741	5,541,375	5,886,903 2,227,991	755,343 337,485	6,642,247 2,565,475
86-113 Latimer	1,760,331	280,864	2,078,327 2,041,195	2,387,819	350,494	2,738,313
114-141 Latimer	2,070,031	322,851	2,392,882	2,589,251	378,157	2,967,408
1-30 Winslow	2,226,739	341,124	2,567,863	2,779,953	399,488	3,179,441
1-25 Padbury	1,497,943	253,529	1,751,472	2,058,200	316,254	2,374,454
1-15 Brockley 1-20 Northchurch	860,619 1,395,252	183,294 249,250	1,043,913 1,644,502	1,196,773 1,756,844	220,523 287,430	1,417,297 2,044,274
21-40 Northchurch	1,426,222	253,685	1,679,908	1,776,987	290,095	2,067,082
41-56 Northchurch	1,222,694	226,860	1,449,553	1,505,470	256,477	1,761,947
57-76 Northchurch	1,257,379	225,177	1,482,556	1,705,585	275,154	1,980,739
1-16 Chadwell	917,994	189,929	1,107,923	1,276,558	229,573	1,506,132
Houses adjacent to Chadwell 1-20 Darvell	491,349 1,147,492	140,847 215,795	632,196 1,363,288	693,041 1,595,698	163,252 265,434	856,294 1,861,132
1-27 Wolverton	1,617,778	267,218	1,884,997	2,222,856	334,434	2,557,290
28-59 Wolverton	2,507,327	376,123	2,883,450	3,051,227	432,155	3,483,382
60-84 Wolverton	1,881,424	301,926	2,183,350	2,333,413	349,651	2,683,065
85-104 Wolverton 105-125 Wolverton	1,198,354	219,981 269,816	1,418,335	1,646,560 1,972,153	269,958 308,979	1,916,518
126-151 Wolverton	1,598,978 2,068,173	325,741	1,868,795 2,393,914	2,499,265	369,813	2,281,132 2,869,079
152-175 Wolverton	1,508,855	253,189	1,762,045	2,046,702	312,824	2,359,526
176-192 Wolverton	1,018,601	200,123	1,218,724	1,399,576	242,181	1,641,757
1-30 Soane House	1,721,239	280,797	2,002,036	2,393,547	355,256	2,748,803
31-35 Soane House 1-12 Lees	299,589 688,495	120,014 163,726	419,603 852,221	411,640 957,419	132,086 193,712	543,726 1,151,131
1-43 Missenden	3,928,117	524,470	4,452,587	4,707,704	606,641	5,314,345
44-75 Missenden	2,476,357	371,688	2,848,045	3,031,084	429,490	3,460,574
256-299 Missenden	3,279,624	461,849	3,741,473	4,038,314	540,705	4,579,019
300-313 Missenden	1,334,678	245,149	1,579,827	1,583,461	271,032	1,854,493
1-36 Michael Faraday 37-56 Michael Faraday	2,062,205 1,198,354	314,584 219,981	2,376,790 1,418,335	2,868,975 1,646,560	404,205 269,958	3,273,181 1,916,518
57-76 Michael Faraday	1,256,308	227,986	1,484,294	1,704,513	277,964	1,982,477
77-105 Michael Faraday	1,748,151	281,964	2,030,114	2,398,049	354,008	2,752,057
	133,338,665	19,972,932	153,311,597	178,290,112	24,810,237	203,100,348
	Construction	Soft Costs	Total (£)	Construction	Soft Costs	Total (£)
Total	165,927,553	25,398,554	191,326,106	224,214,526	31,595,973	255,810,499

### SUMMARY OF STRENGTHING WORKS, INCLUDING DESIGN FEES ONLY

PMASE IA		De	ecent Homes			Decent Homes +	
1-22 Bindenham	PUAGE 44			Total (£)	Construction	Design Fees	Total (£)
1.12 Calhiern   0		0			0		
1-68 Chartridge	1-172 Chiltern						
69-76 Chartridge		991 040	118 177	1 109 217	644 583	78 611	723 195
106-119 Chartridge			110,177	1,100,217		70,011	720,100
120-149 Chartridge	5		00.004	040 044		10.000	100.000
1-41 Bradenham			26,221	212,041	,	18,802	139,662
1-12 Red Lion	1-41 Bradenham	-	61,588	557,108	-	41,806	364,097
External Works							
Drainage							
Path Number of THE ESTATE	Drainage				0		
1-240 Wendrower		1,672,380	205,986	1,878,366	1,087,734	139,219	1,226,954
241-471 Wendover							
1-215 Taplow   0							
166-255 Missendem							
1-61 Gayhurst							
62-79 Gayhurst		-	113 030	1 011 160	-	76 132	660 292
145-182 Galyhurst			110,000	1,011,100		70,130	500,232
1-20 Hambleton			00.070	0.40 700		04.000	405.070
1-31 Calwerton	•		32,973	249,763		24,068	165,070
1-18 Galiskell		0					
19-42 Gaitskell							
A3-66 Gaitskell					-		
1-30 Foxcote	43-66 Gaitskell	0			0		
1-81 Ravenstone							
1-B1 Latimer		-	113.030	1.011.160	-	76.138	660.292
86-113 Latimer	1-61 Latimer	,	131,225	1,184,205	684,870	87,972	772,842
114-14   Latimer   309,700   43,890   353,590   201,432   31,168   232,601   1-30 Winslow   340,670   47,529   388,199   221,576   33,535   255,111   1-25 Padbury   0			40,251	318,981		28,801	210,091
1-30 Winslow   340,670   47,529   388,199   221,576   33,535   255,111     1-25 Padbury   0			43.890	353.590	-	31.168	232.601
1-15 Brockley	1-30 Winslow		·		221,576		
1-20 Northchurch	•						
21-40 Northchurch		-	36,612	284,372	-	26,435	187,580
57-76 Northchurch	21-40 Northchurch		40,251	318,981	181,289	28,801	210,091
1-16 Chadwell		•	32,973	249,763		24,068	165,070
1-20 Darvell							
1-27 Wolverton	Houses adjacent to Chadwell	0			0		
28-59 Wolverton         495,520         65,724         561,244         322,292         45,369         367,661           60-84 Wolverton         309,700         43,890         353,590         201,432         31,168         232,601           85-104 Wolverton         0         0         0         0         0           105-125 Wolverton         278,730         40,251         318,981         181,289         28,801         210,091           126-151 Wolverton         433,580         58,446         492,026         282,005         40,636         322,641           152-175 Wolverton         0         0         0         0         0         0         1         1         1         1         1         210,091         1         1         26,191         322,641         1         1         20,005         40,636         322,641         1         322,641         1         1         1         1         20,005         40,636         322,641         1         322,641         1         20,005         40,636         322,641         1         20,005         40,636         322,641         1         20,005         40,636         322,641         322,641         322,601         3         322,601         <		_			_		
85-104 Wolverton         0         0         0         105-125 Wolverton         278,730         40,251         318,981         181,289         28,801         210,091           126-151 Wolverton         433,580         58,446         492,026         282,005         40,636         322,641           152-175 Wolverton         0         0         0         0         0         0           176-192 Wolverton         0         0         0         0         0         0         0         0         1-30 Soane House         0         0         0         0         0         0         0         0         0         0         1-12 Lees         0         0         0         0         0         0         0         0         0         1-12 Lees         0         0         0         0         0         0         0         0         0         1-12 Lees         0         0         0         0         0         0         0         0         1-12 Lees         0         0         0         0         0         1-12 Lees         0         0         0         0         1-14-75 Missenden         464,550         62,085         526,635         302,148         43,002		-	65,724	561,244		45,369	367,661
105-125 Wolverton         278,730         40,251         318,981         181,289         28,801         210,091           126-151 Wolverton         433,580         58,446         492,026         282,005         40,636         322,641           152-175 Wolverton         0         0         0         0         0         0           1-30 Soane House         0         0         0         0         0         0           1-12 Lees         0         0         0         0         0         0         0           1-43 Missenden         526,490         69,363         595,853         342,435         47,736         390,171         44-75 Missenden         464,550         62,085         526,635         302,148         43,002         345,151         256-299 Missenden         650,370         83,918         734,288         423,008         57,203         480,211         300-313 Missenden         185,820         29,334         215,154         120,859         21,701         142,560         1-36 Michael Faraday         0         0         0         0         0         0         0         0         0         0         0         0         0         0         0         0         0         0 <t< td=""><td></td><td>•</td><td>43,890</td><td>353,590</td><td></td><td>31,168</td><td>232,601</td></t<>		•	43,890	353,590		31,168	232,601
126-151 Wolverton       433,580       58,446       492,026       282,005       40,636       322,641         152-175 Wolverton       0       0       0       0       0       0       0       0       1-76-192 Wolverton       0			40 251	318 981		28 801	210 091
176-192 Wolverton       0       1-12 Lees       0       0       0       0       0       0       0       0       0       1-12 Lees       0       0       0       0       0       0       0       0       1-12 Model       0       0       0       0       0       0        0			·				
1-30 Soane House 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0							
31-35 Soane House							
1-43 Missenden         526,490         69,363         595,853         342,435         47,736         390,171           44-75 Missenden         464,550         62,085         526,635         302,148         43,002         345,151           256-299 Missenden         650,370         83,918         734,288         423,008         57,203         480,211           300-313 Missenden         185,820         29,334         215,154         120,859         21,701         142,560           1-36 Michael Faraday         0         0         0         0         0         0           57-76 Michael Faraday         0 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>							
44-75 Missenden         464,550         62,085         526,635         302,148         43,002         345,151           256-299 Missenden         650,370         83,918         734,288         423,008         57,203         480,211           300-313 Missenden         185,820         29,334         215,154         120,859         21,701         142,560           1-36 Michael Faraday         0					-		
256-299 Missenden         650,370         83,918         734,288         423,008         57,203         480,211           300-313 Missenden         185,820         29,334         215,154         120,859         21,701         142,560           1-36 Michael Faraday         0 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>							
1-36 Michael Faraday 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0							
37-56 Michael Faraday 57-76 Michael Faraday 77-105 Michael Faraday  8,083,170 1,084,772 9,167,942 5,257,383 752,743 6,010,126  Sub-Total Contingency 10% 975,555 129,076 1,104,631 634,512 89,196 723,708 Inflation 6% pa 2,427,655 321,203 2,748,859 1,578,974 221,963 1,800,937		185,820			120,859		
57-76 Michael Faraday     0     0     0       77-105 Michael Faraday     0     0     0       8,083,170     1,084,772     9,167,942     5,257,383     752,743     6,010,126       Sub-Total Contingency     9,755,550     1,290,758     11,046,308     6,345,117     891,962     7,237,079       Contingency     10%     975,555     129,076     1,104,631     634,512     89,196     723,708       Inflation     6% pa     2,427,655     321,203     2,748,859     1,578,974     221,963     1,800,937	_						
77-105 Michael Faraday 0 0 0 752,743 6,010,126 8,083,170 1,084,772 9,167,942 5,257,383 752,743 6,010,126							
Sub-Total         9,755,550         1,290,758         11,046,308         6,345,117         891,962         7,237,079           Contingency         10%         975,555         129,076         1,104,631         634,512         89,196         723,708           Inflation         6% pa         2,427,655         321,203         2,748,859         1,578,974         221,963         1,800,937		0	1.001.770	0.40=0.00	0	750 740	0.040.405
Contingency         10%         975,555         129,076         1,104,631         634,512         89,196         723,708           Inflation         6% pa         2,427,655         321,203         2,748,859         1,578,974         221,963         1,800,937		8,083,170	1,084,7/2	9,167,942	5,257,383	/52,/43	6,010,126
Inflation 6% pa <u>2,427,655 321,203 2,748,859 1,578,974 221,963 1,800,937</u>							
	· -	13,158,760	1,741,038	2,748,859 <b>14,899,798</b>	8,558,603	1,203,121	9,761,724

#### NOTES & QUALIFICATIONS:

BPTW reports dated 28th April , 3rd and 4th May 2005 have been used as the basis for the Decent Homes, Decent Homes + and New Build costs.

A 6 year programme of works commencing in May 2006 has been used for the estimate. However this will result in some homes not meeting the Decent Homes standard until after 2010.

Inflation of 6% per annum has been assumed.

No allowances have been made for dealing with ground contamination, diversion of services, legal fees and Section 106 matters.

No further ANDC staff time has been allowed for Phase 2. It is assumed that any staff required will be funded from other sources.

	1	Decent Homes	•	Decent Ho	mes +
42-256 Bradenham					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		116,418 126,041 231,146 673,165 140,292 735,000 375,000 27,933 67,697 1,350,000 0 0 0		116,418 126,041 231,146 673,165 140,292 735,000 375,000 27,933 67,697 1,350,000 0 0 0	
IMPROVEMENT WORKS TOTAL £		5,429,025	5,429,025	5,429,025	5,429,025
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		456,232 228,299 0 0 93,007 88,190 13,910		0 228,299 0 0 93,007 88,190 13,910	
PPM WORKS TOTAL £		879,638	879,638	423,406	423,406
SUB-TOTAL £		6,308,663		5,852,431	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 see mech services 119,799 269,908 373,687 139,058	0	0 see mech services 119,799 269,908 373,687 139,058	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				967,500 645,000 967,500 2,042,500	
DECENT HOMES TOTAL £		902,452	902,452	5,524,952	5,524,952
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		37,868 1,950,164 0 9,199,147	1,988,032	37,868 2,643,539 0 14,058,791	2,681,407
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	90,152 55,797 50,000 17,574 27,029 65,732 29,700		137,776 55,797 50,000 17,574 27,029 65,732 29,700	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		7,871 23,796		11,987 36,242	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	22,998 432,360 135,227		35,147 660,763 206,664	
Building Services Structural	5.60% 5.00%	123,384 102,696		237,764 102,696	
Consolidating Brief Feasibility Stage 1A Site Model		12,250 4,000 2,000		12,250 4,000 2,000	
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		52,179 109,567 21,740 6,522		52,179 109,567 21,740 6,522	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 45,996 200,000		2,000 70,294 200,000	
			1,640,570		2,155,424
42-256 Bradenham	TOTAL £		10,839,717	_	16,214,215

		Decent Home	es	Decent H	omes +
1-172 Chiltern					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		116,418 126,041 115,582 673,165 119,339 492,000 300,000 27,933 41,391 1,000,000 0 0 0 0 0 567,290 800,000		116,418 126,041 115,582 673,165 119,339 492,000 300,000 27,933 41,391 1,000,000 0 0 0 0 0 567,290	
IMPROVEMENT WORKS TOTAL £		4,379,158	4,379,158	4,379,158	4,379,158
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		422,938 186,826 0 0 94,762 83,340 11,261		0 186,826 0 0 94,762 83,340 11,261	
PPM WORKS TOTAL £		799,126	799,126	376,189	376,189
SUB-TOTAL £		5,178,285		4,755,347	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 113,749 257,866 298,950 111,246		see mech services 113,749 257,866 298,950 111,246	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				774,000 516,000 774,000 1,634,000	
DECENT HOMES TOTAL £		781,810	781,810	4,479,810	4,479,810
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		30,294 1,560,131 0 7,550,521	1,590,426	30,294 2,114,831 0 11,380,283	2,145,126
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management	15% 0.98% 2004-2005	73,995 36,677 0 14,221		111,527 14,221	
SBDS Staff Programme Management  NCD Staff  NCD Consultation & Communication	2005-2008	21,873 0 53,194 29,700		21,873 0 53,194 29,700	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		0 6,527 19,732		0 9,719 29,384	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	18,876 354,874 110,993		28,451 534,873 167,290	
Building Services Structural	5.60% 5.00%	108,275 79,171		199,779 79,171	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		42,225 88,673 17,593 5,278		42,225 88,673 17,593 5,278	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 37,753		2,000 56,901	
4.470 Obilion	TOTAL 5		1,121,631	_	1,491,853
1-172 Chiltern	TOTAL £		8,672,152		12,872,137

	ĺ	Decent Homes		Decent H	omes +
1-68 Chartridge					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BNIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 212,242 0 0 56,458 46,042 206,511 15,598 377,906 293,907 0 0		0 0 0 0 212,242 0 0 56,458 46,042 206,511 15,598 377,906 293,907 0 0	
IMPROVEMENT WORKS TOTAL £		1,634,751	1,634,751	1,634,751	1,634,751
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		160,789 170,366 0 0 49,742 19,843 3,891		0 170,366 0 0 49,742 19,843 3,891	
PPM WORKS TOTAL £		404,631	404,631	243,842	243,842
SUB-TOTAL £		2,039,383		1,878,594	
STRUCTURAL STRENGTHENING WORKS	(32 Units)	991,040	991,040	644,583	644,583
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 37,937 119,628 115,329 43,039		see mech services 37,937 119,628 115,329 43,039	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				306,000 204,000 306,000 646,000	
DECENT HOMES TOTAL £		315,934	315,934	1,777,934	1,777,934
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		20,167 775,236 0	795,403	20,167 994,536 0	1,014,703
TOTAL £		4,141,759		5,315,813	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	15% 0.98% 2004-2005 2005-2008	40,589 15,484 10,000 0 9,341 0 22,717		52,095 15,484 10,000 0 9,341 0 22,717	
NCD Consultation & Communication  Planning Fees (Bigs Only)		3,671		4,595	
Building Control Inspection (Blgs Only)		11,096		13,890	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	10,354 194,663 60,884		13,290 249,843 78,142	
Building Services Structural	5.60% 5.00%	36,206 78,102		72,382 60,779	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		18,032 37,867 7,513 2,254 0		18,032 37,867 7,513 2,254 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 20,709		2,000 26,579	
1-68 Chartridae	TOTAL £	_	581,482 4,723,241	-	696,803 6,012,616

		Decent Homes		Decent Ho	omes +
69-76 Chartridge					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 36,117 0 0 0 0 100,038 7,228 48,162 0 0 0 0 28,870		0 0 0 0 36,117 0 0 0 100,038 7,228 48,162 0 0 0 0 37,090 28,870	
IMPROVEMENT WORKS TOTAL £		257,504	257,504	257,504	257,504
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		18,770 22,982 0 0 13,336 2,205 649		22,982 0 0 13,336 2,205 649	
PPM WORKS TOTAL £		57,941	57,941	39,171	39,171
SUB-TOTAL £		315,445		296,675	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 4,463 11,384 13,561 5,063		see mech services 4,463 11,384 13,561 5,063	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				36,000 24,000 36,000 76,000	
DECENT HOMES TOTAL £		34,471	34,471	206,471	206,471
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		2,373 91,204 0 443,493	93,577	2,373 117,004 0 622,523	119,377
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	4,346 6,807 5,000 0 2,577 0 6,269		6,101 6,807 5,000 0 2,577 0 6,269	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		563 1,698		731 2,206	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	1,109 20,844 6,519		1,556 29,259 9,151	
Building Services Structural	5.60% 5.00%	4,988 7,475		9,244 7,475	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		4,975 10,448 2,073 622 0		4,975 10,448 2,073 622 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 2,217		2,000 3,113	
69-76 Chartridge	TOTALO		90,531	_	109,606
69-76 Chartridge	TOTAL £		534,024		732,129

		Decent Hom	es	Decent H	omes +
77-105 Chartridge					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings		0 0 0 0 57,059 0 0 0 76,414 7,278 0 0 75,000		0 0 0 57,059 0 0 0 76,414 7,278 0	
Elitratice Folderings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		75,000 0 0 93,291 104,652		93,291 104,652	
IMPROVEMENT WORKS TOTAL £		413,694	413,694	413,694	413,694
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		58,346 61,367 0 0 19,659 8,819 649		0 61,367 0 0 19,569 8,819 649	
PPM WORKS TOTAL £		148,839	148,839	90,404	90,404
SUB-TOTAL £		562,533		504,097	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,179 52,705 49,184 18,355		see mech services 16,179 52,705 49,184 18,355	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				130,500 87,000 130,500 275,500	
DECENT HOMES TOTAL £		136,424	136,424	759,924	759,924
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		8,601 330,615 0	339,216	8,601 424,140 0	432,741
TOTAL £		1,038,173	000,210	1,696,762	102,7 11
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	10,174 8,051 5,000 0 3,547 0 8,627		16,628 8,051 5,000 0 3,547 0 8,627	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,067 3,222		1,571 4,746	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	2,595 48,794 15,261		4,242 79,748 24,942	
Building Services Structural	5.60% 5.00%	16,464 7,657		31,892 7,652	
Consolidating Brief Feasibility Stage 1A Site Model				,,,,,	
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		6,847 14,379 2,853 856 0		6,847 14,379 2,853 856 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 5,191		2,000 8,484	
77-105 Chartridge	TOTAL £	_	162,585 1,200,758	-	232,065 1,928,827
100 Gridianudo	IOIALL	1	.,230,730	ľ	.,020,027

106-119 Chartridge		ı	Decent Homes		Decent Hon	nes +
REPORT VOING   Reductionment of Stantown     0   0   0   0   0   0   0   0   0	106-119 Chartridge		Book Homes		Decent Flori	ies i
Mechanical & Electrical grow surracordingency)	IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works		0 0 0 43,365 0 0 0 90,548 172,839 7,278 84,204 0 0		0 0 43,365 0 0 0 90,548 172,839 7,278 84,204 0 0	
PPM WORKS INC. DECENT HOMES EXTERNALS   Window Requires   Concrete Register   Concre						
Mindow Repairs   A3787   S. 20   Roding   Roding   S. 200   S. 200   S. 200   S. 200   Roding   S. 200   S. 2	IMPROVEMENT WORKS TOTAL £		500,284	500,284	500,284	500,284
SIB-TOTAL £  STRUCTURAL STENDING WORKS (6 Units)  DECENT HOMES INTERNALS Extact Verifiation to Devellings Charles of Devellings Abelestor Removal to Develling	Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		38,260 0 0 18,934 3,969 1,297	100 040	38,260 0 0 18,934 3,969 1,297	00.400
STRUCTURAL STRENGTHENING WORKS   (6 Units)	PPM WORKS TOTAL £		103,240	103,246	02,400	62,460
DECENT HOMES INTERNALS		(0.11-24-)		405		,
Extract Veritation to Dwellings   Covertual Mechanical Services to Dwellings   Replacement Electrical Works to Dwellings   25,673   25,672   25,8		(6 Units)	185,820	185,820	120,859	120,859
Works to Sitchers         63,000           Works to Stathroons         42,000           Works to Stathroons         42,000           Window Replacement         33,000           CIP Works         66,083         36,000           DAYWORKS & PRELIMINARIES         36,000         36,000           Dayworks         4,152         4,152           Provisional Work / Items (inc main contingency)         159,607         204,757           Main Preliminaries         0         163,759         0           TOTAL £         1,019,192         1,259,595           FEES           SBDS Staff SW Corner Monitoring         0,98%         9,988         12,344           SBDS Staff SW Corner Monitoring         7,706         7,706         7,706           SBDS Staff SW Corner Monitoring         3,98%         7,706         7,706           SBDS Staff Programme Management         2004-2005         0         0         0           SBDS Staff Programme Management         2004-2005         0         0         0         0           NCD Staff         7,706         7,702         7,972         7,972         7,972         7,972         7,972         7,972         7,972         1,255         1,254	Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings		7,811 25,679 23,732		7,811 25,679 23,732	
DAYWORKS & PRELIMINARIES   Dayworks   Provisional Work / Items (inc main contingency)   To Table	Works to Kitchens Works to Bathrooms Window Replacement				42,000 63,000	
Dayworks   Provisional Work / Items (inc main contingency)   Main Preliminaries   159,607   204,757   204,757   0 163,759   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757   0 163,759   0 24,757	DECENT HOMES TOTAL £		66,083	66,083	367,083	367,083
SBDS Staff SW Corner Monitoring   SBDS Staff SW Corner Additional Services   SBDS Staff Programme Management   2004-2005   0	Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		159,607 0	163,759	204,757 0	208,909
Building Control Inspection (Blgs Only)   3,222   3,730	SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	2004-2005	7,706 5,000 0 3,279 0 7,972		7,706 5,000 0 3,279 0 7,972	
Levitt Bernstein (Architect) 4, 70% BPTW QS & Demolition Surveyor 1.47% 14,982 59,201 BPTW QS & Demolition Surveyor 1.47% 14,982 18,516 Building Services 5.60% 8,309 15,757 Structural 5.00% 25,575 22,327 Consolidating Brief Feasibility Stage 1A Site Model Site Engineer (Alan Conisbee) 6,329 6,329 31,291 31,29						
Structural	Levitt Bernstein (Architect)	4.70%	47,902		59,201	
Feasibility Stage 1A Site Model  Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW) Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep   6,329 13,291 13,291 2,637 291 13,291 2,637 791 0 0 0 0 0 0 6,298 167,694						
Site Architect (Full Time)   13,291   2,637   2,637   791   791   791   0   0   0   0   0   0   0   0   0	Feasibility Stage 1A					
Planning Supervisor 0.50% 5,096 6,298  Condition / Measured Surveys? / Site Prep 167,694 167,694 15	Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		13,291 2,637 791 0		13,291 2,637 791 0	
	Planning Supervisor	0.50%				
106-119 (Chartridge	100 110 01	TOTAL -			_	191,562
1,100,000 1,100,000 1,45	106-119 Chartridge	TOTAL £		1,186,886		1,451,157

		Decent Hor	mes	Decent H	omes +
120-149 Chartridge					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 0 77,225 0 0 0 0 108,330 7,278 0 0 75,000 0 0 93,390 108,261		0 0 0 77,225 0 0 0 108,330 7,278 0 0 75,000 0 0 93,390	
Mechanical & Electrical (prov sums/contingency)  IMPROVEMENT WORKS TOTAL £		469,484	469,484	469,484	469,484
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		63,378 62,605 0 0 19,659 8,819 1,946		0 62,605 0 0 19,659 8,819 1,946	
PPM WORKS TOTAL £		156,407	156,407	93,028	93,028
SUB-TOTAL £		625,891		562,512	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,737 54,442 50,853 18,988		see mech services 16,737 54,442 50,853 18,988	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				135,000 90,000 135,000 285,000	
DECENT HOMES TOTAL £		141,020	141,020	786,020	786,020
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		8,897 342,016 0	350,913	8,897 438,766 0	447,663
TOTAL £		1,117,824		1,796,196	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	10,955 8,037 5,000 0 3,566 0 8,667		17,603 8,037 5,000 0 3,566 0 8,667	
Planning Fees (Blgs Only)		1,151		1,655	
Building Control Inspection (Blgs Only)  Levitt Bernstein (Lead)  Levitt Bernstein (Architect)	0.25% 4.70%	3,476 2,795 52,538		5,000 4,490 84,421	
BPTW QS & Demolition Surveyor  Building Services	1.47% 5.60%	16,432 16,836		26,404 32,796	
Structural  Consolidating Brief Feasibility Stage 1A Site Model	5.00%	10,261		10,261	
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW) Incidental Expenses & Disbursements Planning Supervisor	0.50%	6,883 14,455 2,867 860 0 2,000 5,589		6,883 14,455 2,867 860 0 2,000 8,981	
Condition / Measured Surveys? / Site Prep	TOTAL £		172,366 1,290,190	-	243,946 2,040,142

		Decent Homes		Decent H	omes +
1-41 Bradenham					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 127,127 0 0 28,153 0 102,405 15,598 179,790 159,894 0 0		0 0 0 127,127 0 28,153 0 102,405 15,598 179,790 159,894 0 0	
IMPROVEMENT WORKS TOTAL £		880,411	880,411	880,411	880,411
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		85,310 108,488 0 0 34,464 12,347 2,954		0 108,488 0 0 34,464 12,347 2,954	
PPM WORKS TOTAL £		243,562	243,562	158,253	158,253
SUB-TOTAL £		1,123,973		1,038,664	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS	(16 Units)	495,520	495,520	322,292	322,292
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 22,874 71,641 69,500 25,950		see mech services 22,874 71,641 69,500 25,950	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				184,500 123,000 184,500 389,500	
DECENT HOMES TOTAL £		189,965	189,965	1,071,465	1,071,465
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		12,160 467,421 0 2,289,039	479,581	12,160 599,646 0 3,044,226	611,806
FEES		2,209,039		3,044,220	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	22,433 10,566 10,000 0 5,505 0 13,394		29,833 10,566 10,000 0 5,505 0 13,394	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		2,075 6,270		2,747 8,302	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	5,723 107,585 33,649		7,611 143,079 44,750	
Building Services Structural	5.60% 5.00%	22,414 39,384		44,226 30,722	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		10,631 22,326 4,430 1,329		10,631 22,326 4,430 1,329	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 11,445 300,000		2,000 15,221 300,000	
1-41 Bradenham	TOTAL £		631,158	_	706,672 3,750,899
Siddomidii	- IOIAL L	1	_,0_0,107		5,750,000

		Decent Homes		Decent H	omes +
1-28 Arklow					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 0 0 81,756 0 0 0 0 56,262 0 0 0 0		0 0 0 81,756 0 0 0 56,262 0 0 0 0	
Mechanical & Electrical (prov sums/contingency)  IMPROVEMENT WORKS TOTAL £		101,043 329,486	329,486	101,043 329,486	329,486
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		0 0 0 0 0 0 7,937 1,946		0 0 0 0 0 7,937 1,946	
PPM WORKS TOTAL £		9,883	9,883	9,883	9,883
SUB-TOTAL £		339,369		339,369	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 15,621 50,452 47,463 17,722		see mech services 15,621 50,452 47,463 17,722	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				126,000 84,000 126,000 266,000	
DECENT HOMES TOTAL £		131,259	131,259	733,259	733,259
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		8,304 319,215 0 798,146	327,519	8,304 409,515 0 1,490,446	417,819
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication Planning Fees (Bigs Only)	0.98% 2004-2005 2005-2008	7,822 8,668 5,000 0 1,148 0 9,796		14,606 8,668 5,000 0 1,148 0 9,796	
Building Control Inspection (Blgs Only)		2,460		4,238	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	1,995 37,513 11,733		3,726 70,051 21,910	
Building Services Structural	5.60% 5.00%	15,859 6,901		30,755 6,901	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		7,775 16,328 3,240 972 0		7,775 16,328 3,240 972 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	2,000 3,991		2,000 7,452	
1.28 Arklow	TOTALO		144,016	_	215,969
1-28 Arklow	TOTAL £		942,162	I	1,706,416

		Decent Homes		Decent H	omes +
1-12 Red Lion					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BNIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 11,360 0 0 0 0 42,090 0 0 0 0 0 0 42,090		0 0 0 0 11,360 0 0 0 42,090 0 0 0 0 0 0 42,290 0 0 0	
IMPROVEMENT WORKS TOTAL £		143,991	143,991	143,991	143,991
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		28,484 48,595 0 0 0 3,528 649		0 48,565 0 0 3,528 649	
PPM WORKS TOTAL £		81,255	81,255	52,741	52,741
SUB-TOTAL £		225,247		196,732	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 6,695 20,841 20,341 7,595		see mech services 6,695 20,841 20,341 7,595	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				54,000 36,000 54,000 114,000	
DECENT HOMES TOTAL £		55,472	55,472	313,472	313,472
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		3,559 136,806 0 421,084	140,365	3,559 175,506 0 689,270	179,065
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	4,127 5,318 2,000 0 1,418 0 3,447		6,755 5,318 2,000 0 1,418 0 3,447	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		563 1,698		731 2,206	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	1,053 19,791 6,190		1,723 32,396 10,132	
Building Services Structural  Consolidating Brief Feasibility Stage 1A Site Model	5.60% 5.00%	7,235 2,672		13,619 2,672	
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		2,738 5,750 1,140 342		2,738 5,750 1,140 342 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	1,000 2,105		1,000 3,446	
1-12 Red Lion	TOTAL £		68,587 489,671	-	96,834 786,104

		Decent Hor	mes	Decent H	omes +
External Works					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
Mechanical & Electrical (prov sums/contingency)  IMPROVEMENT WORKS TOTAL £		0 4,316,941	4,316,941	0 4,316,941	4,316,941
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		0 0 0 0 0 0	0	0 0 0 0 0 0	0
TTM WOTING TOTAL 2			Ů		· ·
SUB-TOTAL £  STRUCTURAL STRENGTHENING WORKS		4,316,941 0	0	4,316,941 0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 0 0 0		0 0 0 0	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				0 0 0 0	
DECENT HOMES TOTAL £		0	0	0	0
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		0 0 0 4,316,941	0	0 0 0 4,316,941	0
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication Planning Fees (Bigs Only)	0.98% 2004-2005 2005-2008	42,306 26,473 20,000 0 17,917 0 43,579		42,306 26,473 20,000 0 17,917 0 43,579	
Building Control Inspection (Blgs Only)		0		0	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	10,792 202,896 63,459		10,792 202,896 63,459	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	5.60% 5.00%	0		0 0	
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		34,590 72,635 14,413 4,324 0		34,590 72,635 14,413 4,324 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	50,000 21,585		50,000 21,585	
External Works	TOTAL £	_	624,969 4,941,910	-	624,969 4,941,910
	. 517.22	1	.,2,0 . 0		.,5,5 10

	Ī	Decent	Homes	Decent H	lomes +
Drainage					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors		0 0 0		0 0 0 0 0	
Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings		0 0 0		0 0 0	
Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls		0		0 0 0	
Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 29,337 0		0 0 0 29,337 0	
Mechanical & Electrical (prov sums/contingency)  IMPROVEMENT WORKS TOTAL £		29,337	29,337	29,337	29,337
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs		0		0	
Roofing Drainage		0 224,232		0 224,232	
Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		0 0 0		0 0 0	
PPM WORKS TOTAL £		224,232	224,232	224,232	224,232
SUB-TOTAL £		253,568		253,568	
STRUCTURAL STRENGTHENING WORKS DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 0 0 0		0 0 0 0	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				0 0 0 0	
DECENT HOMES TOTAL £		0	0	0	0
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency)		0		0	
Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		0	0	0	0
TOTAL £ FEES		253,568		253,568	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	2,485 in environmental		2,485	
NCD Consultation & Communication		in environmental in environmental 0		0	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		0		0	
Levitt Bernstein (Lead) Levitt Bernstein (Architect) BPTW QS & Demolition Surveyor	0.25% 4.70% 1.47%	634 11,918 3,727		634 11,918 3,727	
Building Services Structural	5.60% 5.00%	0		0	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Engineer ( Alan Conisbee) Site Architect (Full Time) Site Clerk of Works Site QS (BPTW)		in environmental in environmental in environmental in environmental in environmental			
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50%	in environmental 1,268		1,268	
Drainage	TOTAL £		20,032	-	20,032
		1		1	

		Decent Ho	mes	Decent H	omes +
1-240 Wendover					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		146,198 158,285 209,650 845,369 161,563 753,487 418,606 35,078 66,662 1,451,162 0 0 0 11,412 2,269,901 723,041 1,116,278		146,198 158,285 209,650 845,369 161,563 753,487 418,606 35,078 66,662 1,451,162 0 0 0 11,412 2,269,901 723,041 1,116,278	
IMPROVEMENT WORKS TOTAL £		8,366,693	8,366,693	8,366,693	8,366,693
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		549,730 257,767 87,221 0 118,025 107,366 158,976		0 257,767 87,221 0 118,025 107,366 158,976	
PPM WORKS TOTAL £		1,279,085	1,279,085	729,355	729,355
SUB-TOTAL £		9,645,778		9,096,048	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 146,225 330,554 417,139 155,227		see mech services 146,225 330,554 417,139 155,227	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				1,080,000 720,000 1,080,000 2,280,000	
DECENT HOMES TOTAL £		1,049,146	1,049,146	6,209,146	6,209,146
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		42,271 2,176,927 0	2,219,198	42,271 2,950,927 0	2,993,198
TOTAL £		12,914,122		18,298,392	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management	0.98% 2004-2005 2005-2008	126,558 30,498 19,483 48,708 5,845		179,324 30,498 19,483 48,708 5,845	
NCD Staff NCD Consultation & Communication		10,000 10,000		10,000 10,000	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		11,063 33,448		15,515 46,910	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	32,285 645,706 193,712		45,746 914,920 274,476	
Building Services Structural	6.00% 5.00%	154,722 112,555		291,522 112,555	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		92,545 194,832 24,354 14,612		92,545 194,832 24,354 14,612	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 240	12,354 64,571 66,000		12,354 91,492 66,000	
1-240 Wendover	TOTAL £	_	1,903,851 14,817,972	-	2,501,690 20,800,082

	ĺ	Decent H	omes	Decent H	omes +
241-471 Wendover					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		140,716 152,349 201,788 813,667 155,505 725,231 402,908 33,763 64,163 1,396,744 0 0 0 10,984 2,184,780 695,927 1,074,418		140,716 152,349 201,788 813,667 155,505 725,231 402,908 33,763 64,163 0 0 0 10,984 2,184,780 695,927 1,074,418	
IMPROVEMENT WORKS TOTAL £		8,052,942	8,052,942	8,052,942	8,052,942
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		529,115 248,101 83,950 0 113,599 103,340 153,014		0 248,101 83,950 0 113,599 103,340 153,014	
PPM WORKS TOTAL £		1,231,119	1,231,119	702,004	702,004
SUB-TOTAL £		9,284,061		8,754,946	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 140,741 318,159 401,496 149,406		see mech services 140,741 318,159 401,496 149,406	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				1,039,500 693,000 1,039,500 2,194,500	
DECENT HOMES TOTAL £		1,009,803	1,009,803	5,976,303	5,976,303
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		40,686 2,095,292 0	2,135,978	40,686 2,840,267 0	2,880,953
TOTAL £		12,429,842		17,612,202	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	121,812 inc in wendover above inc in wendover above inc in wendover above inc in wendover above		172,600 inc in wendover above inc in wendover above inc in wendover above inc in wendover above	
NCD Consultation & Communication  Planning Fees (Blgs Only)  Publisher Control beneating (Plgs Only)		10,643		15,011	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	32,178 31,075		45,386 44,031	
Architect Quantity Surveyor	5.00% 1.50%	621,492 186,448		880,610 264,183	
Building Services Structural	6.00% 5.00%	148,919 108,334		280,589 108,334	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		inc in wendover above inc in wendover above inc in wendover above inc in wendover above		inc in wendover above inc in wendover above inc in wendover above inc in wendover above	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 231	12,000 62,149 63,525		12,000 88,061 63,525	
241-471 Wendover	TOTAL £	_	1,398,575 13,828,418		1,974,330 19,586,532

		Decent Hom	es	Decent H	omes +
1-215 Taplow					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		130,969 141,797 187,811 757,310 144,734 674,999 375,001 31,424 59,718 1,300,000 0 0 0 10,223 2,033,453 647,724 999,999		130,969 141,797 187,811 757,310 144,734 674,999 375,001 31,424 59,718 1,300,000 0 0 0 10,223 2,033,453 647,724 999,999	
IMPROVEMENT WORKS TOTAL £		7,495,162	7,495,162	7,495,162	7,495,162
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		492,466 230,916 78,135 0 105,731 96,182 142,416		0 230,916 78,135 0 105,731 96,182 142,416	
PPM WORKS TOTAL £		1,145,847	1,145,847	653,381	653,381
SUB-TOTAL £		8,641,009		8,148,543	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 see mech services 130,993 296,122 373,687 139,058	0	see mech services 130,993 296,122 373,687 139,058	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				967,500 645,000 967,500 2,042,500	
DECENT HOMES TOTAL £		939,860	939,860	5,562,360	5,562,360
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		37,868 1,950,164 0 11,568,901	1,988,032	37,868 2,643,539 0 16,392,310	2,681,407
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Phase 2 Design Team Procurement NCD Staff NCD Consultation & Communication Planning Fees (Bigs Only)	0.98% 2004-2005 2005-2008	113,375 15,350 9,306 23,264 2,792 5,000 10,000		160,645 15,350 9,306 23,264 2,792 5,000 10,000	
Building Control Inspection (Blgs Only)		29,892		41,830	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	28,922 578,445 173,534		40,981 819,615 245,885	
Building Services Structural	6.00% 5.00%	138,605 100,830		261,155 100,830	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		44,201 93,055 11,632 6,979 0		44,201 93,055 11,632 6,979 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 215	11,632 57,845 59,125		11,632 81,962 59,125	
4 O45 Toology	TOTAL	_	1,523,671	_	2,059,073
1-215 Taplow	TOTAL £		13,092,571		18,451,383

		Decent Ho	omes	Decent Hor	nes +
76-165 Missenden					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		54,824 59,357 78,619 317,013 60,586 282,558 156,977 13,154 24,998 544,186 0 0 0 4,280 851,213 271,140 418,604		54,824 59,357 78,619 317,013 60,586 282,558 156,977 13,154 24,998 544,186 0 0 0 4,280 851,213 271,140 418,604	
IMPROVEMENT WORKS TOTAL £		3,137,510	3,137,510	3,137,510	3,137,510
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		206.149 96.663 32.708 0 44,259 40,262 59,616	479,657	0 96,663 32,708 0 44,259 40,262 59,616	273.508
					5,555
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		3,617,167	0	3,411,018	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 54,834 123,958 156,427 58,210		see mech services 54,834 123,958 156,427 58,210	o O
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				405,000 270,000 405,000 855,000	
DECENT HOMES TOTAL £		393,430	393,430	2,328,430	2,328,430
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		15,852 816,348 0 4,842,796	832,199	15,852 1,106,598 0 6,861,897	1,122,449
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Phase 2 Design Team Procurement NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	47,459 12,960 7,700 19,250 2,310 10,000 10,000		67,247 12,960 7,700 19,250 2,310 10,000 10,000	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		4,175 12,620		5,939 17,954	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	12,107 242,140 72,642		17,155 343,095 102,928	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	6.00% 5.00%	58,021 42,208		109,321 42,208	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		36,575 76,999 9,625 5,775 0		36,575 76,999 9,625 5,775 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 90	9,625 24,214 24,750		9,625 34,309 24,750	
76 165 Micropidos	TOTAL	_	741,154	_	965,724
76-165 Missenden	TOTAL £		5,583,949	1	7,827,621

		Decent Hon	nes	Decent H	omes +
166-255 Missenden					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		54,824 59,357 78,619 317,013 60,586 282,558 156,977 13,154 24,998 544,186 0 0 0 4,280 851,213 271,140 418,604		54,824 59,357 78,619 317,013 60,586 282,558 156,977 13,154 24,998 544,186 0 0 0 4,280 851,213 271,140 418,604	
IMPROVEMENT WORKS TOTAL £		3,137,510	3,137,510	3,137,510	3,137,510
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		206,149 96,663 32,708 0 44,259 40,262 59,616		0 96,663 32,708 0 44,259 40,262 59,616	
PPM WORKS TOTAL £		479,657	479,657	273,508	273,508
SUB-TOTAL £		3,617,167		3,411,018	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 54,834 123,958 156,427 58,210		see mech services 54,834 123,958 156,427 58,210	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				405,000 270,000 405,000 855,000	
DECENT HOMES TOTAL £		393,430	393,430	2,328,430	2,328,430
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries'Site overheads on defined Prov Sums		15,852 816,348 0	832,199	15,852 1,106,598 0	1,122,449
TOTAL £		4,842,796		6,861,897	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	47,459 12,960 7,700 19,250 2,310		67,247 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Blgs Only)		4,259		5,939	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	12,874 12,107		17,954 17,155	
Architect Quantity Surveyor	5.00% 1.50%	242,140 72,642		343,095 102,928	
Building Services Structural	6.00% 5.00%	58,021 42,208		109,321 42,208	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 90	5000 24,214 24,750		5000 34,309 24,750	
166-255 Missenden	TOTAL £	_	625,893 5,468,689	-	850,125 7,712,022

	Ì	Decent Homes		Decent Ho	mes +
1-61 Gayhurst					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mcchanical & Electrical (prov sums/contingency)		0 0 0 0 169,597 0 0 46,266 217,915 321,377 25,688 335,155 250,772 0 2,901 576,933 208,805 220,131		0 0 0 0 169,597 0 46,266 217,915 321,377 25,685 335,155 250,772 0 2,901 576,933 208,805 220,131	
IMPROVEMENT WORKS TOTAL £		2,375,539	2,375,539	2,375,539	2,375,539
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		141,199 165,633 22,169 0 60,203 17,747 39,559		0 165,633 22,169 0 60,203 17,747 39,559	
PPM WORKS TOTAL £		446,510	446,510	305,311	305,311
SUB-TOTAL £	(20 Linite)	2,822,049	000 400	2,680,851	504454
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(29 Units)	898,130 see mech services 51,159 106,251 103,416 38,609	898,130	584,154 see mech services 51,159 106,251 103,416 38,609	584,154
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				274,500 183,000 274,500 579,500	
DECENT HOMES TOTAL £		299,435	299,435	1,610,935	1,610,935
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £ FEES		18,091 695,432 0 4,733,137	713,523	18,091 892,157 0 5,786,187	910,248
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	46,385 12,960 7,700 19,250 2,310		46,385 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		4,175 12,620		5,015 15,160	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	11,833 236,657 70,997		11,833 236,657 70,997	
Building Services Structural	6.00% 5.00%	38,562 85,674		73,332 69,976	
Consolidating Brief Feasibility Stage 1A Site Model	5.00%	65,074		05,576	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 61	5000 23,666 16,775		5000 23,666 16,775	
1-61 Gavhurst	TOTAL £	_	632,563 5,365,701	_	655,015 6,441,202

MPROVEMENT WORKS   Refurbalment of Stairtower 1   0   0   0   0   0   0   0   0   0		ĺ	Decent Home	s	Decent Ho	mes +
Part	62-79 Gayhurst				Booking	
PPM WORK'S NO. DECENT HOMES EXTERNALS   Window Regalis   A 1,655   A 48,875   A 48,875	Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 50,045 0 0 13,652 64,303 94,832 7,580 98,898 73,998 0 856 170,243 61,615		0 0 0 50,045 0 0 13,652 64,303 94,832 7,580 98,898 73,998 0 856 170,243 61,615	
Municow Repairs   1,665   0   0   0   0   17,765   0   0   17,765	IMPROVEMENT WORKS TOTAL £		700,979	700,979	700,979	700,979
SUB-TOTAL ©   832,736   791,071	Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		48,875 6,542 0 17,765 5,237 11,673		48,875 6,542 0 17,765 5,237 11,673	
STRUCTURAL STRENGTHENING WORKS   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	PPM WORKS TOTAL £		131,757	131,757	90,092	90,092
DECENT HOMES INTERNALS						
Extrad Ventilation to Divellings   Soverhauf Mechanical Services to Divellings   15,096   31,353   30,516   30,516   31,353   30,516   31,353   30,516   31,353   30,516   31,353   30,516   31,353   30,516   30,516   31,353   3			0	0	0	0
Works to Ritchens         81,000           Works of Bathrooms         54,000           Window Replacement         54,000           CHP Works         88,358         88,358           DECENT HOMES TOTAL £         88,358         88,358         475,358           DAYWORKS & PRELIMINARIES         Dayworks         5,338         5,338           Provisional Work / Items (inc main contingency)         925,209         263,259         263,259           Main Preliminaries         0         210,548         0         2           TOTAL £         1,131,641         1,535,026         1         1         1,535,026           FEES         SBDS Staff SW Corner Additional Services         11,090         15,043         15,043         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,960         12,250         19,250	Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings		15,096 31,353 30,516		15,096 31,353 30,516	
DAYWORKS & PRELIMINARIES   Dayworks   Provisional Work / Items (inc main contingency)   Main Preliminaries   205,209   263,259   263,2	Works to Kitchens Works to Bathrooms Window Replacement				54,000 81,000	
Dayworks   Frovisional Work / Items (inc main contingency)   Main Preliminaries   205,209   263,259   26	DECENT HOMES TOTAL £		88,358	88,358	475,358	475,358
SBDS Staff SW Corner     0.98%       SBDS Staff SW Corner Monitoring     11,090       SBDS Staff SW Corner Additional Services     12,960       SBDS Staff Programme Management     2004-2005       SBDS Staff Programme Management     2005-2008       NCD Staff NCD Consultation & Communication     2,310       Planning Fees (Bigs Only)     1,151       Building Control Inspection (Bigs Only)     1,151       Lead Design Fees     0.25%       Architect     5.00%       Quantity Surveyor     1.50%       Building Services     6.00%       Structural     5.00%       Consolidating Brief       Feasibility Stage 1A       Site Based Engineer     10000       Site Based Clerk of Works     5000       Site Based Quantity Surveyor     5000       Incidental Expenses & Disbursements     5000       Planning Supervisor     0.50%       5,658     7,675	Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		205,209 0	210,548	263,259 0	268,598
Planning Fees (BIgs Only)	SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	2004-2005	12,960 7,700 19,250		12,960 7,700 19,250	
Lead Design Fees     0.25%     2,829     3,838       Architect     5.00%     56,582     76,751       Quantity Surveyor     1.50%     16,975     23,025       Building Services     6.00%     11,379     21,639       Structural     5.00%     12,030     12,030       Consolidating Brief     Feasibility Stage 1A     1000     1000       Site Based Engineer     2000     2000       Site Based Architect     20000     2000       Site Based Clerk of Works     5000     5000       Site Based Quantity Surveyor     3000     3000       Incidental Expenses & Disbursements     5000     5000       Planning Supervisor     0.50%     5,658     7,675	Planning Fees (Blgs Only)					
Building Services   6.00%   11,379   21,639	Lead Design Fees Architect	5.00%	2,829 56,582		3,838 76,751	
Consolidating Brief   Feasibility Stage 1A   Site Model	Building Services	6.00%	11,379		21,639	
Site Based Architect         20000         20000           Site Based Clerk of Works         5000         5000           Site Based Quantity Surveyor         3000         3000           Incidental Expenses & Disbursements         5000         5000           Planning Supervisor         0.50%         5,658         7,675	Consolidating Brief Feasibility Stage 1A	3.00 /6	12,000		12,000	
Planning Supervisor 0.50% 5,658 7,675	Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		20000 5000 3000		20000 5000 3000	
	Planning Supervisor		5,658		7,675	
						256,150
62-79 Gavhurst TOTAL £ 1,342,981 1,7	62-79 Gayhurst	TOTAL £		1,342,981		1,791,176

	ı	Decent Home	es	Decent Hom	nes +
80-144 Gayhurst					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 180,718 0 49,300 232,205 342,451 27,372 357,133 267,216 0 3,091 614,765 222,498 234,566		0 0 0 0 180,718 0 49,300 232,205 342,451 27,372 357,133 267,216 0 3,091 614,765 222,498 234,566	
IMPROVEMENT WORKS TOTAL £		2,531,313	2,531,313	2,531,313	2,531,313
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		150,457 176,495 23,622 0 64,151 18,911 42,153		0 176,495 23,622 0 64,151 18,911 42,153	
PPM WORKS TOTAL £		475,789	475,789	325,332	325,332
SUB-TOTAL £		3,007,102		2,856,644	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 see mech services 54,514 113,218 110,197 41,140	0	0 see mech services 54,514 113,218 110,197 41,140	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				292,500 195,000 292,500 617,500	
DECENT HOMES TOTAL £		319,070	319,070	1,716,570	1,716,570
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		19,278 741,034 0 4,086,483	760,312	19,278 950,659 0 5,543,151	969,937
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	40,048 12,960 7,700 19,250 2,310		54,323 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		3,587 10,842		4,847 14,652	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	10,216 204,324 61,297		13,858 277,158 83,147	
Building Services Structural	6.00% 5.00%	41,091 43,441		78,141 43,441	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 65	5000 20,432 17,875		5000 27,716 17,875	
80-144 Gayhurst	TOTAL £	_	538,373 4,624,856	_	700,377 6,243,528

		Decent Homes		Decent H	omes +
145-162 Gayhurst					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 50,045 0 0 13,652 64,303 94,832 7,580 98,888 73,998 0 856 170,243 61,615 64,957		0 0 0 0 50,045 0 13,652 64,303 94,832 7,598 98,898 73,998 0 856 170,243 61,615 64,957	
IMPROVEMENT WORKS TOTAL £		700,979	700,979	700,979	700,979
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		41,665 48,875 6,542 0 17,765 5,237 11,673		0 48.875 6,542 0 17,765 5,237 11,673	
PPM WORKS TOTAL £		131,757	131,757	90,092	90,092
SUB-TOTAL £		832,736		791,071	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(7 Units)	216,790 see mech services 15,096 31,353 30,516 11,393	216,790	141,003 see mech services 15,096 31,353 30,516 11,393	141,003
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				81,000 54,000 81,000 171,000	
DECENT HOMES TOTAL £		88,358	88,358	475,358	475,358
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,338 205,209 0 1,348,431	210,548	5,338 263,259 0 1,676,029	268,598
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	13,215 12,960 7,700 19,250 2,310		16,425 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,319 3,984		1,571 4,746	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	3,371 67,422 20,226		4,190 83,801 25,140	
Building Services Structural	6.00% 5.00%	11,379 22,869		21,639 19,080	
Consolidating Brief Feasibility Stage 1A Site Model Site Based Engineer		10000		10000	
Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		20000 5000 3000		20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 18	5000 6,742 4,950		5000 8,380 4,950	
145-162 Gavhurst	TOTAL £		240,697	_	275,143 1,951,172
170-102 Gaylluist	TOTAL		1,505,120	]	1,331,172

		Decent Hom	es	Decent Home	s +
1-20 Hambleton					
MPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 109,887 82,220 951 189,158 68,461 72,174		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 109,887 82,220 0 951 189,158 68,461 72,174	
MPROVEMENT WORKS TOTAL £		778,865	778,865	778,865	778,865
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		46,295 54,306 7,268 0 19,739 5,819 12,970	146.397	0 54,306 7,268 0 19,739 5,819 12,970	100,102
					,
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		925,262	0	878,967 0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,774 34,836 33,907 12,659	Ü	see mech services 16,774 34,836 33,907 12,659	·
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		5,932 228,010 0	233,942	5,932 292,510 0	298,442
TOTAL £		1,257,379		1,705,585	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	12,322 12,960 7,700 19,250 2,310		16,715 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,235 3,730		1,655 5,000	
Lead Design Fees Architect	0.25% 5.00%	3,143 62,869		4,264 85,279	
Quantity Surveyor  Building Services	1.50%	18,861 12,643		25,584 24,043	
Structural  Consolidating Brief Feasibility Stage 1A Site Model	5.00%	13,367		13,367	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 6,287 5,500		5000 8,528 5,500	
1 00 Hambleter	TOTAL	_	225,177	_	275,154
1-20 Hambleton	TOTAL £	1	1,482,556		1,980,739

	Ī	Decent Home	es	Decent Ho	omes +
1-31 Calverton				Boomerie	311100
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 86,189 0 0 23,512 110,744 163,323 13,054 170,325 127,441 0 1,474 293,196 106,114 111,870		0 0 0 0 0 86,189 0 0 23,512 110,744 163,323 13,054 170,325 127,441 0 1,474 293,196 106,114	
IMPROVEMENT WORKS TOTAL £		1,207,241	1,207,241	1,207,241	1,207,241
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Grainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		71,757 84,174 11,266 0 30,595 9,019 20,104		0 84,174 11,266 0 30,595 9,019 20,104	
PPM WORKS TOTAL £		226,915	226,915	155,158	155,158
SUB-TOTAL £		1,434,156		1,362,399	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 25,999 53,996 52,556 19,621		see mech services 25,999 53,996 52,556 19,621	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				139,500 93,000 139,500 294,500	
DECENT HOMES TOTAL £		152,172	152,172	818,672	818,672
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		9,194 353,416 0 1,948,938	362,610	9,194 453,391 0 2,643,656	462,585
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	19,100 12,960 7,700 19,250 2,310		25,908 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,823 5,508		2,411 7,286	
Lead Design Fees Architect	0.25% 5.00%	4,872 97,447		6,609 132,183	
Quantity Surveyor	1.50%	29,234		39,655	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	6.00% 5.00%	19,597 20,718		37,267 20,718	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 31	5000 9,745 8,525		5000 13,218 8,525	
1.01 Oakunta	TOTAL		301,789	_	379,000
1-31 Calverton	TOTAL £		2,250,727		3,022,656

	ĺ	Decent Homes	S	Decent Ho	mes +
1-31 Danesfield					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 86,189 0 0 23,512 110,744 163,323 13,054 170,325 127,441 0 1,474 293,196 106,114 111,870		0 0 0 0 86,189 0 0 23,512 110,744 163,323 13,054 170,325 127,441 0 1,474 293,196 106,114	
IMPROVEMENT WORKS TOTAL £		1,207,241	1,207,241	1,207,241	1,207,241
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		71,757 84,174 11,266 0 30,595 9,019 20,104		0 84,174 11,266 0 30,595 9,019 20,104	
PPM WORKS TOTAL £		226,915	226,915	155,158	155,158
SUB-TOTAL £		1,434,156		1,362,399	
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaud Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 see mech services 25,999 53,996 52,556 19,621	0	0 see mech services 25,999 53,996 52,556 19,621	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				139,500 93,000 139,500 294,500	
DECENT HOMES TOTAL £		152,172	152,172	818,672	818,672
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		9,194 353,416 0 1,948,938	362,610	9,194 453,391 0 2,643,656	462,585
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	19,100 12,960 7,700 19,250 2,310		25,908 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,823 5,508		2,411 7,286	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	4,872 97,447 29,234		6,609 132,183 39,655	
Building Services Structural Consolidating Brief	6.00% 5.00%	19,597 20,718		37,267 20,718	
Feasibility Stage 1A Site Model Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 31	5000 9,745 8,525		5000 13,218 8,525	
1-31 Danesfield	TOTAL £	_	301,789 2,250,727	_	379,000 3,022,656

		Decent Homes	3	Decent H	omes +
1-18 Gaitskell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 50,045 0 0 13,652 64,303 94,832 7,580 0 73,998 45,776 856 170,243 61,615 64,957		0 0 0 0 50,045 0 13,652 64,303 94,832 7,580 0 73,998 45,776 856 170,243 61,615 64,957	
IMPROVEMENT WORKS TOTAL £		647,856	647,856	647,856	647,856
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		41,665 48,875 6,542 0 17,765 5,237 11,673		0 48,875 6,542 0 17,765 5,237 11,673	
PPM WORKS TOTAL £		131,757	131,757	90,092	90,092
SUB-TOTAL £		779,613		737,948	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 15,096 31,353 30,516 11,393		see mech services 15,096 31,353 30,516 11,393	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				81,000 54,000 81,000 171,000	
DECENT HOMES TOTAL £		88,358	88,358	475,358	475,358
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		5,338 205,209 0	210,548	5,338 263,259 0	268,598
TOTAL £		1,078,519		1,481,904	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	10,569 12,960 7,700 19,250 2,310		14,523 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		1,067		1,403	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	3,222 2,696		4,238 3,705	
Architect Quantity Surveyor	5.00% 1.50%	53,926 16,178		74,095 22,229	
Building Services Structural	6.00% 5.00%	11,379 12,030		21,639 12,030	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 18	5000 5,393 4,950		5000 7,410 4,950	
1.18 Gaitskell	TOTALO		206,630	_	251,440
1-18 Gaitskell	TOTAL £		1,285,149		1,733,344

	ĺ	Decent Home	es	Decent Ho	omes +
19-42 Gaitskell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 66,727 0 0 18,203 85,737 126,443 10,107 0 98,664 61,034 1,141 226,990 82,153 86,609		0 0 0 0 0 66,727 0 0 18,203 85,737 126,443 10,107 0 98,664 61,034 1,141 226,990 82,153 86,609	
IMPROVEMENT WORKS TOTAL £		863,808	863,808	863,808	863,808
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		55,554 65,167 8,722 0 23,687 6,983 15,564		0 65,167 8,722 0 23,687 6,983 15,564	
PPM WORKS TOTAL £		175,676	175,676	120,122	120,122
SUB-TOTAL £		1,039,484		983,931	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 20,128 41,804 40,688 15,190		see mech services 20,128 41,804 40,688 15,190	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				108,000 72,000 108,000 228,000	
DECENT HOMES TOTAL £		117,810	117,810	633,810	633,810
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		7,118 273,612 0	280,730	7,118 351,012 0	358,130
TOTAL £		1,438,025		1,975,872	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	14,093 12,960 7,700 19,250 2,310		19,364 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		1,403 4,238		1,823 5,508	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	3,595		4,940	
Architect Quantity Surveyor	5.00% 1.50%	71,901 21,570		98,794 29,638	
Building Services Structural	6.00% 5.00%	15,172 16,040		28,852 16,040	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 24	5000 7,190 6,600		5000 9,879 6,600	
10 42 Coitakall	TOTAL		247,022	_	306,657
19-42 Gaitskell	TOTAL £		1,685,047		2,282,528

	1	Decent Home	es	Decent Ho	omes +
43-66 Gaitskell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 66,727 0 0 18,203 85,737 126,443 10,107 0 98,664 61,034 1,141 226,990 82,153 86,609		0 0 0 0 0 66,727 0 18,203 85,737 126,443 10,107 0 98,664 61,034 1,141 226,990 82,153 86,609	
IMPROVEMENT WORKS TOTAL £		863,808	863,808	863,808	863,808
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		55,554 65,167 8,722 0 23,687 6,983 15,564		0 65,167 8,722 0 23,687 6,983 15,564	
PPM WORKS TOTAL £		175,676	175,676	120,122	120,122
SUB-TOTAL £		1,039,484		983,931	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 20,128 41,804 40,688 15,190		see mech services 20,128 41,804 40,688 15,190	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				108,000 72,000 108,000 228,000	
DECENT HOMES TOTAL £		117,810	117,810	633,810	633,810
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		7,118 273,612 0	280,730	7,118 351,012 0	358,130
TOTAL £		1,438,025		1,975,872	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	14,093 12,960 7,700 19,250 2,310		19,364 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		1,403		1,823	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	4,238 3,595		5,508 4,940	
Architect Quantity Surveyor	5.00% 1.50%	71,901 21,570		98,794 29,638	
Building Services Structural	6.00% 5.00%	15,172 16,040		28,852 16,040	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 24	5000 7,190 6,600		5000 9,879 6,600	
40 00 Octobelle	TOTAL 6		247,022	_	306,657
43-66 Gaitskell	TOTAL £	1	1,685,047	1	2,282,528

	I	Decent Homes		Decent H	omes +
1-35 Emberton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 97,310 0 0 26,546 125,033 184,396 14,739 192,302 143,885 0 1,664 331,027 119,806 126,305		0 0 0 97,310 0 26,546 125,033 184,396 14,739 192,302 143,885 0 1,664 331,027 119,806 126,305	
IMPROVEMENT WORKS TOTAL £		1,363,014	1,363,014	1,363,014	1,363,014
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		81,016 95,036 12,720 0 34,543 10,183 22,698		0 95,036 12,720 0 34,543 10,183 22,698	
PPM WORKS TOTAL £		256,194	256,194	175,179	175,179
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		1,619,209 0		1,538,193	
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 29,354 60,964 59,337 22,153	0	see mech services 29,354 60,964 59,337 22,153	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				157,500 105,000 157,500 332,500	
DECENT HOMES TOTAL £		171,807	171,807	924,307	924,307
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		10,380 399,018 0 2,200,414	409,399	10,380 511,893 0 2,984,773	522,274
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	21,564 12,960 7,700 19,250 2,310		29,251 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		2,075 6,270		2,663 8,048	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	5,501 110,021 33,006		7,462 149,239 44,772	
Building Services Structural	6.00% 5.00%	22,126 23,391		42,076 23,391	
Consolidating Brief Feasibility Stage 1A Site Model	3.55 /6			25,531	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 35	5000 11,002 9,625		5000 14,924 9,625	
1-35 Emberton	TOTAL £		329,801 2,530,215	_	416,670 3,401,443
. oo Emborion	- OTAL 2	1	_,,		5,701,770

	ı	Decent Hor	nes	Decent Home	s <b>+</b>
1-30 Foxcote					
MPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 83,408 0 0 22,754 107,171 158,054 12,633 0 123,330 76,293 1,427 283,738 102,681 108,261		0 0 0 0 0 83,408 0 0 22,754 107,171 158,054 12,633 0 123,330 76,293 1,427 283,738 102,691 108,261	
MPROVEMENT WORKS TOTAL £		1,079,761	1,079,761	1,079,761	1,079,76
PM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PM WORKS TOTAL £		69,442 81,459 10,903 0 29,608 8,728 19,455	219,595	0 81,459 10,903 0 29,608 8,728 19,455	150.153
		4 000 050		1 000 011	, -
SUB-TOTAL £  TRUCTURAL STRENGTHENING WORKS		1,299,356	0	1,229,914	
ECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 25,160 52,255 50,860 18,988		see mech services 25,160 52,255 50,860 18,988	
ECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				135,000 90,000 135,000 285,000	
ECENT HOMES TOTAL £		147,263	147,263	792,263	792,26
AYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		8,897 342,016 0 1,797,532	350,913	8,897 438,766 0 2,469,840	447,66
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	17,616 12,960 7,700 19,250 2,310		24,204 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,655 5,000		2,243 6,778	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	4,494 89,877 26,963		6,175 123,492 37,048	
Building Services Structural	6.00% 5.00%	18,965 20,050		36,065 20,050	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 30	5000 8,988 8,250		5000 12,349 8,250	
			287,076	_	361,87
1-30 Foxcote	TOTAL £	_	2,084,608		2,831,71

		Decent Homes		Decent H	omes +
1-81 Ravenstone					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 0 225,203 0 0 61,435 289,363 426,746 34,110 445,042 332,992 0 3,852 766,092 2277,266		0 0 0 225,203 0 61,435 289,363 426,746 34,110 445,042 332,992 0 3,852 766,092 277,266	
Mechanical & Electrical (prov sums/contingency)  IMPROVEMENT WORKS TOTAL £		292,305 3,154,405	3,154,405	292,305 3,154,405	3,154,405
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		187,493 219,939 29,437 0 79,942 23,566 52,529		0 219,939 29,437 0 79,942 23,566 52,529	
PPM WORKS TOTAL £		592,906	592,906	405,413	405,413
SUB-TOTAL £		3,747,311		3,559,818	
STRUCTURAL STRENGTHENING WORKS	(29 Units)	898,130	898,130	584,154	584,154
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 67,933 141,087 137,323 51,267		see mech services 67,933 141,087 137,323 51,267	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				364,500 243,000 364,500 769,500	
DECENT HOMES TOTAL £		397,610	397,610	2,139,110	2,139,110
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		24,023 923,442 0	947,465	24,023 1,184,667 0	1,208,690
TOTAL £		5,990,517		7,491,772	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Phase 2 Design Team Procurement	0.98% 2004-2005 2005-2008	58,707 6,726 3,511 8,778 1,053		73,419 6,726 3,511 8,778 1,053	
NCD Staff NCD Consultation & Communication		5,000 3,000		5,000 3,000	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		5,183 15,668		6,443 19,478	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	14,976 299,526 89,858		18,729 374,589 112,377	
Building Services Structural	6.00% 5.00%	51,205 99,041		97,375 83,342	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000 0		10000 20000 5000 3000 0	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 81	4,389 29,953 22,275		4,389 37,459 22,275	
1-81 Ravenstone	TOTAL £		756,850 6,747,367	-	915,945 8,407,717

		Decent Homes	S	Decent Ho	omes +
1-61 Latimer					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 169,597 0 46,266 217,915 321,377 25,688 335,155 250,772 0 2,901 576,933 208,805 220,131		0 0 0 0 169,597 0 46,266 217,915 321,377 25,688 335,155 250,772 0 2,901 576,933 208,805 220,131	
IMPROVEMENT WORKS TOTAL £		2,375,539	2,375,539	2,375,539	2,375,539
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		141,199 165,633 22,169 0 60,203 17,747 39,559		0 165,633 22,169 0 60,203 17,747 39,559	
PPM WORKS TOTAL £		446,510	446,510	305,311	305,311
SUB-TOTAL £	(34 Units)	2,822,049	4 050 000	2,680,851	004.070
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(34 UTIIIS)	1,052,980 see mech services 51,159 106,251 103,416 38,609	1,052,980	684,870 see mech services 51,159 106,251 103,416 38,609	684,870
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				274,500 183,000 274,500 579,500	
DECENT HOMES TOTAL £		299,435	299,435	1,610,935	1,610,935
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		18,091 695,432 0 4,887,987	713,523	18,091 892,157 0 5,886,903	910,248
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	47,902 12,960 7,700 19,250 2,310		57,692 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		4,259 12,874		5,099 15,414	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	12,220 244,399 73,320		14,717 294,345 88,304	
Building Services Structural	6.00% 5.00%	38,562 93,417		73,332 75,011	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 61	5000 24,440 16,775		5000 29,435 16,775	
1-61 Latimer	TOTAL £	_	653,388 5,541,375	_	755,343 6,642,247

	Î	Decent Homes		Decent Ho	omes +
62-85 Latimer					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 0 66,727 0 0 18,203 85,737 126,443 10,107 131,864 98,664 0 1,141 226,990 82,153 86,609		0 0 0 0 66,727 0 18,203 85,737 126,443 10,107 131,864 98,664 0 1,141 226,990 82,153 86,609	
IMPROVEMENT WORKS TOTAL £		934,638	934,638	934,638	934,638
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		55,554 65,167 8,722 0 23,687 6,983 15,564	175,676	0 65,167 8,722 0 23,687 6,983 15,564	120,122
			,		,
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(9 Units)	1,110,314 278,730	278,730	1,054,761 181,289	181,289
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 20,128 41,804 40,688 15,190		see mech services 20,128 41,804 40,688 15,190	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				108,000 72,000 108,000 228,000	
DECENT HOMES TOTAL £		117,810	117,810	633,810	633,810
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		7,118 273,612 0 1,787,585	280,730	7,118 351,012 0 2,227,991	358,130
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	17,518 12,960 7,700 19,250 2,310		21,834 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,655 5,000		2,075 6,270	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	4,469 89,379 26,814		5,570 111,400 33,420	
Building Services Structural	6.00% 5.00%	15,172 29,976		28,852 25,104	
Consolidating Brief Feasibility Stage 1A Site Model	3.00 /0			20,.04	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 24	5000 8,938 6,600		5000 11,140 6,600	
62 05 Letimo-	TOTAL		290,741	_	337,485
62-85 Latimer	TOTAL £		2,078,327		2,565,475

	1	Decent Hon	nes	Decent Home	es +
86-113 Latimer					
MPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Arreas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 77,848 0 0 21,237 100,027 147,517 11,791 153,842 115,108 0 1,331 264,822 95,845 101,044		0 0 0 0 77,848 0 0 21,237 100,027 147,517 11,791 153,842 115,108 0 1,331 264,822 95,845 101,044	
MPROVEMENT WORKS TOTAL £		1,090,412	1,090,412	1,090,412	1,090,412
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		64,812 76,028 10,176 0 27,634 8,146 18,158	204.955	0 76,028 10,176 0 27,634 8,146 18,158	140.143
					,
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		1,295,367	0	1,230,554	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 23,483 48,771 47,470 17,722	Ü	see mech services 23,483 48,771 47,470 17,722	3
DECENT HOMES + Works to Klitchens Works to Bathrooms Window Replacement CHP Works				126,000 84,000 126,000 266,000	
DECENT HOMES TOTAL £		137,446	137,446	739,446	739,446
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		8,304 319,215 0	327,519	8,304 409,515 0	417,819
TOTAL £		1,760,331		2,387,819	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	17,251 12,960 7,700 19,250 2,310		23,401 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,655 5,000		2,159 6,524	
Lead Design Fees Architect	0.25% 5.00%	4,401 88,017		5,970 119,391	
Quantity Surveyor	1.50%	26,405		35,817	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	6.00% 5.00%	17,701 18,713		33,661 18,713	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 28	5000 8,802 7,700		5000 11,939 7,700	
00.440   51700	TOTAL 5		280,864		350,494
86-113 Latimer	TOTAL £		2,041,195		2,738,313

		Decent Home	es	Decent Home	s <b>+</b>
114-141 Latimer					
MPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 77,848 0 0 21,237 100,027 147,517 11,791 153,842 115,108 0 1,331 264,822 95,845 101,044		0 0 0 0 77,848 0 0 21,237 100,027 147,517 11,791 153,842 115,108 0 1,331 264,822 95,845 101,044	
MPROVEMENT WORKS TOTAL £		1,090,412	1,090,412	1,090,412	1,090,412
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		64,812 76,028 10,176 0 27,634 8,146 18,158	204.955	76,028 10,176 0 27,634 8,146 18,158	140,143
			204,933		140,143
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(10 Units)	1,295,367 309,700	309,700	1,230,554 201,432	201,432
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings  Overhaul Mechanical Services to Dwellings  Replacement Electrical Works to Dwellings  Asbestos Removal to Dwellings  BWIC with services to Dwellings	(10 Office)	see mech services 23,483 48,771 47,470 17,722	309,700	see mech services 23,483 48,771 47,470 17,722	201,432
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				126,000 84,000 126,000 266,000	
DECENT HOMES TOTAL £		137,446	137,446	739,446	739,446
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		8,304 319,215 0	327,519	8,304 409,515 0	417,819
TOTAL £		2,070,031		2,589,251	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	20,286 12,960 7,700 19,250 2,310		25,375 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,907 5,762		2,411 7,286	
Lead Design Fees Architect	0.25% 5.00%	5,175 103,502		6,473 129,463	
Quantity Surveyor  Building Services	1.50% 6.00%	31,050 17,701		38,839 33,661	
Structural  Consolidating Brief Feasibility Stage 1A Site Model	5.00%	34,198		28,785	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 28	5000 10,350 7,700		5000 12,946 7,700	
			322,851		378,157
114-141 Latimer	TOTAL £		2,392,882		2,967,408

		Decent Homes		Decent Ho	omes +
1-30 Winslow					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 83,408 0 0 22,754 107,171 158,054 12,633 164,831 123,330 0 1,427 283,738 102,691 108,261		0 0 0 0 83,408 0 0 22,754 107,171 158,054 12,633 164,831 123,330 0 1,427 283,738 102,691 108,261	
IMPROVEMENT WORKS TOTAL £		1,168,298	1,168,298	1,168,298	1,168,298
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		69,442 81,459 10,903 0 29,608 8,728 19,455		0 81,459 10,903 0 29,608 8,728 19,455	
PPM WORKS TOTAL £		219,595	219,595	150,153	150,153
SUB-TOTAL £		1,387,893		1,318,451	
STRUCTURAL STRENGTHENING WORKS	(11 Units)	340,670	340,670	221,576	221,576
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 25,160 52,255 50,860 18,988		see mech services 25,160 52,255 50,860 18,988	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				135,000 90,000 135,000 285,000	
DECENT HOMES TOTAL £		147,263	147,263	792,263	792,263
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		8,897 342,016 0	350,913	8,897 438,766 0	447,663
TOTAL £		2,226,739		2,779,953	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	21,822 12,960 7,700 19,250 2,310		27,244 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Blgs Only)		2,075		2,495	
Building Control Inspection (Blgs Only)		6,270		7,540	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	5,567 111,337 33,401		6,950 138,998 41,699	
Building Services Structural	6.00% 5.00%	18,965 37,083		36,065 31,129	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 30	5000 11,134 8,250		5000 13,900 8,250	
1-30 Winslow	TOTAL £	_	341,124 2,567,863	_	399,488 3,179,441

		Decent Hom	es	Decent H	omes +
1-25 Padbury					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 69,507 0 0 18,962 89,310 131,712 10,528 0 102,775 63,578 1,189 236,448 85,576 90,218		0 0 0 0 0 69,507 0 18,962 89,310 131,712 10,528 0 102,775 63,578 1,189 236,448 85,576 90,218	
IMPROVEMENT WORKS TOTAL £		899,801	899,801	899,801	899,801
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		57,868 67,883 9,086 0 24,674 7,274 16,213		0 67,883 9,086 0 24,674 7,274 16,213	
PPM WORKS TOTAL £		182,996	182,996	125,128	125,128
SUB-TOTAL £		1,082,796		1,024,928	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 20,967 43,546 42,384 15,823		see mech services 20,967 43,546 42,384 15,823	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				112,500 75,000 112,500 237,500	
DECENT HOMES TOTAL £		122,719	122,719	660,219	660,219
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		7,415 285,013 0	292,428	7,415 365,638 0	373,053
TOTAL £ FEES		1,497,943		2,058,200	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	14,680 12,960 7,700 19,250 2,310		20,170 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,403 4,238		1,991 6,016	
Lead Design Fees	0.25%	3,745		5,145	
Architect Quantity Surveyor	5.00% 1.50%	74,897 22,469		102,910 30,873	
Building Services Structural	6.00% 5.00%	15,804 16,708		30,054 16,708	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 25	5000 7,490 6,875		5000 10,291 6,875	
1.25 Padhury	TOTAL £	_	253,529 1,751,472	_	316,254 2,374,454
1-25 Padbury	TOTAL £		1,/51,4/2	I	2,374,454

	ĺ	Decent Homes		Decent Ho	omes +
1-15 Brockley					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 41,704 0 0 11,377 53,586 79,027 6,317 0 61,665 0 713 141,869 51,346 54,131		0 0 0 0 41,704 0 11,377 53,586 79,027 6,317 0 61,665 0 713 141,869 51,346 54,131	
IMPROVEMENT WORKS TOTAL £		501,734	501,734	501,734	501,734
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		34,721 40,730 5,451 0 14,804 4,364 9,728		0 40,730 5,451 0 14,804 4,364 9,728	
PPM WORKS TOTAL £		109,797	109,797	75,077	75,077
SUB-TOTAL £		611,531		576,810	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 12,580 26,127 25,430 9,494		see mech services 12,580 26,127 25,430 9,494	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				67,500 45,000 67,500 142,500	
DECENT HOMES TOTAL £		73,632	73,632	396,132	396,132
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		4,449 171,008 0 860,619	175,457	4,449 219,383 0 1,196,773	223,832
FEES		000,019		1,190,773	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	8,434 12,960 7,700 19,250 2,310		11,728 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		899		1,151	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	2,714 2,152		3,476 2,992	
Architect Quantity Surveyor	5.00% 1.50%	43,031 12,909		59,839 17,952	
Building Services Structural	6.00% 5.00%	9,482 10,025		18,032 10,025	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 15	5000 4,303 4,125		5000 5,984 4,125	
1-15 Brockley	TOTAL £		183,294	-	220,523 1,417,297
1-10 DIOCKIEV	IOIAL &	1	1,040,913		1,417,297

		Decent Homes	3	Decent Ho	omes +
1-20 Northchurch					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 0 82,220 0 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 105,369 8,422 0 82,220 0 1951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		668,978	668,978	668,978	668,978
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		46,295 54,306 7,268 0 19,739 5,819 12,970	146,397	0 54,306 7,268 0 19,739 5,819 12,970	100.102
			140,397		100,102
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		815,375 247,760	247,760	769,080 161,146	161,146
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(8 Units)	see mech services 16,774 34,836 33,907 12,659	241,700	see mech services 16,774 34,836 33,907 12,659	101,140
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,932 228,010 0 1,395,252	233,942	5,932 292,510 0 1,756,844	298,442
FEES		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		1,100,011	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	13,673 12,960 7,700 19,250 2,310		17,217 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Bigs Only)		1,319		1,655	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	3,984 3,488		5,000 4,392	
Architect Quantity Surveyor	5.00% 1.50%	69,763 20,929		87,842 26,353	
Building Services Structural	6.00% 5.00%	12,643 25,755		24,043 21,424	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 6,976 5,500		5000 8,784 5,500	
1-20 Northchurch	TOTAL £		249,250 1,644,502	_	287,430 2,044,274
		1		I	

		Decent Homes		Decent Ho	omes +
21-40 Northchurch					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 0 82,220 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 105,369 8,422 0 82,220 0 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		668,978	668,978	668,978	668,978
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		46,295 54,306 7,268 0 19,739 5,819 12,970	146,397	0 54,306 7,268 0 19,739 5,819 12,970	100.102
					,
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(9 Units)	815,375 278,730	278,730	769,080 181,289	181,289
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(o omis)	see mech services 16,774 34,836 33,907 12,659	270,730	see mech services 16,774 34,836 33,907 12,659	101,209
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,932 228,010 0	233,942	5,932 292,510 0 1,776,987	298,442
FEES		.,		1,770,007	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	13,977 12,960 7,700 19,250 2,310		17,414 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Blgs Only)		1,403		1,655	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	4,238 3,566		5,000 4,442	
Architect Quantity Surveyor	5.00% 1.50%	71,311 21,393		88,849 26,655	
Building Services Structural	6.00% 5.00%	12,643 27,303		24,043 22,431	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 7,131 5,500		5000 8,885 5,500	
21-40 Northchurch	TOTAL £		253,685	-	290,095 2,067,082

		Decent Homes		Decent H	omes +
41-56 Northchurch					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 44,484 0 0 12,135 57,158 84,296 6,738 87,910 65,776 761 151,327 54,769 57,739		0 0 0 44,484 0 12,135 57,158 84,296 6,738 87,910 65,776 0 761 151,327 54,769 57,739	
IMPROVEMENT WORKS TOTAL £		623,092	623,092	623,092	623,092
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		37,036 43,445 5,815 0 15,791 4,655 10,376	117.117	0 43,445 5,815 0 15,791 4,655 10,376	80,082
FFINI WORKS TOTAL I		117,117	117,117	00,002	60,062
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(7 Units)	740,210 216,790	216,790	703,174 141,003	141,003
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(7 Offics)	see mech services 13,419 27,869 27,125 10,127	216,790	see mech services 13,419 27,869 27,125 10,127	141,003
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				72,000 48,000 72,000 152,000	
DECENT HOMES TOTAL £		78,540	78,540	422,540	422,540
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		4,745 182,408 0 1,222,694	187,154	4,745 234,008 0 1,505,470	238,754
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	11,982 12,960 7,700 19,250 2,310		14,754 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,235 3,730		1,487 4,492	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	3,057 61,135 18,340		3,764 75,274 22,582	
Building Services Structural Consolidating Brief	6.00% 5.00%	10,115 21,533		19,235 17,743	
Feasibility Stage 1A Site Model Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 16	5000 6,113 4,400		5000 7,527 4,400	
41-56 Northchurch	TOTAL £		226,860 1,449,553	-	256,477 1,761,947

		Decent Homes		Decent Hom	nes +
57-76 Northchurch					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 109,887 82,220 0 951 189,158 68,461 72,174		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 109,887 82,220 0 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		778,865	778,865	778,865	778,865
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		46,295 54,306 7,268 0 19,739 5,819 12,970		0 54,306 7,268 0 19,739 5,819 12,970	
PPM WORKS TOTAL £		146,397	146,397	100,102	100,102
SUB-TOTAL £		925,262		878,967	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 16,774 34,836 33,907 12,659		see mech services 16,774 34,836 33,907 12,659	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		5,932 228,010 0	233,942	5,932 292,510 0 1,705,585	298,442
FEES					
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	12,322 12,960 7,700 19,250 2,310		16,715 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Blgs Only)		1,235		1,655	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	3,730 3,143		5,000 4,264	
Architect Quantity Surveyor	5.00% 1.50%	62,869 18,861		85,279 25,584	
Building Services Structural	6.00% 5.00%	12,643 13,367		24,043 13,367	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 6,287 5,500		5000 8,528 5,500	
57 70 Northalium h	TOTAL C		225,177	_	275,154
57-76 Northchurch	TOTAL £	1,	482,556		1,980,739

	1	Decent Homes		Decent Homes +	
1-16 Chadwell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BMIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 44,484 0 0 12,135 57,158 84,296 6,738 0 65,776 0 761 151,327 54,769 57,739		0 0 0 0 44,484 0 0 12,135 57,158 84,296 6,738 0 65,776 0 761 151,327 54,769 57,739	
IMPROVEMENT WORKS TOTAL £		535,183 535	5,183	535,183 535,	183
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		37,036 43,445 5,815 0 15,791 4,655 10,376		0 43,445 5,815 0 15,791 4,655 10,376	
PPM WORKS TOTAL £		117,117 117	7,117	80,082 80,0	082
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		652,300 0	0	615,264 0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 13,419 27,869 27,125 10,127	0	see mech services 13,419 27,869 27,125 10,127	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				72,000 48,000 72,000 152,000	
DECENT HOMES TOTAL £		78,540 78	3,540	422,540 422,5	540
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		4,745 182,408 0 187 917,994	7,154	4,745 234,008 0 238, 1,276,558	754
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	8,996 12,960 7,700 19,250 2,310		12,510 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		983 2,968		1,235 3,730	
Lead Design Fees Architect	0.25% 5.00%	2,295 45,900		3,191 63,828	
Quantity Surveyor  Building Services	1.50% 6.00%	13,770 10,115		19,148 19,235	
Structural  Consolidating Brief Feasibility Stage 1A Site Model	5.00%	10,693		10,693	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 16	5000 4,590 4,400		5000 6,383 4,400	
1-16 Chadwell	TOTAL £	185 	7,923	229.	

		Decent Homes		Decent Ho	mes +
Houses adjacent to Chadwell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 0 0 0 0 0 6,826 32,151 47,416 3,790 0 36,999 0 428 85,121 30,807 32,478		0 0 0 0 0 0 0 0 6,826 32,151 47,416 3,790 0 36,999 0 428 85,121 30,807 32,478	
IMPROVEMENT WORKS TOTAL £		276,018	276,018	276,018	276,018
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		20,833 24,438 3,271 0 8,882 2,618 5,837		0 24,438 3,271 0 8,882 2,618 5,837	
PPM WORKS TOTAL £		65,878	65,878	45,046	45,046
SUB-TOTAL £		341,896		321,064	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 7,548 15,676 15,258 5,696		see mech services 7,548 15,676 15,258 5,696	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				40,500 27,000 40,500 85,500	
DECENT HOMES TOTAL £		44,179	44,179	237,679	237,679
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		2,669 102,605 0	105,274	2,669 131,630 0	134,299
TOTAL £		491,349		693,041	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	4,815 12,960 7,700 19,250 2,310		6,792 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		563		731	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	1,698 1,228		2,206 1,733	
Architect Quantity Surveyor	5.00% 1.50%	24,567 7,370		34,652 10,396	
Building Services Structural	6.00% 5.00%	5,689 4,764		10,819 4,764	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 9	5000 2,457 2,475		5000 3,465 2,475	
Houses adiacent to Chadwell	TOTAL £		140,847 632,196	_	163,252 856,294

		Decent Home	es	Decent Ho	omes +
1-20 Darvell					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 0 82,220 0 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 105,369 8,422 0 82,220 0 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		668,978	668,978	668,978	668,978
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		46,295 54,306 7,268 0 19,739 5,819 12,970	440.007	0 54,306 7,268 0 19,739 5,819 12,970	400.400
PPM WORKS TOTAL £		146,397	146,397	100,102	100,102
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		815,375 0	0	769,080 0	0
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Abestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,774 34,836 33,907 12,659	0	see mech services 16,774 34,836 33,907 12,659	J
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		5,932 228,010 0	233,942	5,932 292,510 0	298,442
TOTAL £		1,147,492		1,595,698	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	11,245 12,960 7,700 19,250 2,310		15,638 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,151 3,476		1,487 4,492	
Lead Design Fees Architect	0.25% 5.00%	2,869 57,375		3,989 79,785	
Quantity Surveyor	1.50%	17,212		23,935	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	6.00% 5.00%	12,643 13,367		24,043 13,367	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 5,737 5,500		5000 7,978 5,500	
1-20 Darvell	TOTAL £		215,795	_	265,434
. 20 5417011	IOIALL	1	.,555,250	1	1,501,102

	ı	Decent Hom	ies	Decent Ho	mes +
1-27 Wolverton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 75,068 0 0 20,478 96,454 142,249 11,370 0 110,997 68,664 1,284 255,364 92,422 97,435		0 0 0 75,068 0 0 20,478 96,454 142,249 11,370 0 110,997 68,664 1,284 255,364 92,422	
IMPROVEMENT WORKS TOTAL £		971,785	971,785	971,785	971,785
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		62,498 73,313 9,812 0 26,647 7,855 17,510		0 73,313 9,812 0 26,647 7,855 17,510	
PPM WORKS TOTAL £		197,635	197,635	135,138	135,138
SUB-TOTAL £		1,169,420		1,106,922	
STRUCTURAL STRENGTHENING WORKS DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 22,644 47,029 45,774 17,089		see mech services 22,644 47,029 45,774 17,089	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				121,500 81,000 121,500 256,500	
DECENT HOMES TOTAL £		132,537	132,537	713,037	713,037
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		8,008 307,814 0 1,617,778	315,822	8,008 394,889 0 2,222,856	402,897
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	15,854 12,960 7,700 19,250 2,310		21,784 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,571 4,746		2,075 6,270	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	4,044 80,889 24,267		5,557 111,143 33,343	
Building Services Structural	6.00% 5.00%	17,068 18,045		32,458 18,045	
Consolidating Brief Feasibility Stage 1A Site Model		.5,5.5		15,5.0	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 27	5000 8,089 7,425		5000 11,114 7,425	
		_	267,218	_	334,434
1-27 Wolverton	TOTAL £		1,884,997		2,557,290

	Ì	Decent Home	es	Decent Home	s <b>+</b>
28-59 Wolverton					
MPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 88,969 0 0 24,271 114,316 168,591 131,552 175,819 131,552 302,653 109,537 115,478		0 0 0 0 88,969 0 0 24,271 114,316 168,591 13,476 175,819 131,552 0 1,522 302,653 109,537 115,478	
MPROVEMENT WORKS TOTAL £		1,246,185	1,246,185	1,246,185	1,246,185
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		74,071 86,890 11,629 0 31,582 9,310 20,752	234,235	86,890 11,629 0 31,582 9,310 20,752	160.163
FFIN WORKS TOTALE		204,200	234,233	100,100	100,103
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(16 Units)	1,480,419	405 500	1,406,348 322,292	200 000
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(16 Units)	495,520 see mech services 26,838 55,738 54,251 20,254	495,520	322,292 see mech services 26,838 55,738 54,251 20,254	322,292
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				144,000 96,000 144,000 304,000	
DECENT HOMES TOTAL £		157,081	157,081	845,081	845,081
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		9,491 364,817 0 2,507,327	374,307	9,491 468,017 0 3,051,227	477,507
FEES		2,007,027		0,001,227	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	24,572 12,960 7,700 19,250 2,310		29,902 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		2,327 7,032		2,747 8,302	
Lead Design Fees Architect	0.25% 5.00%	6,268 125,366		7,628 152,561	
Quantity Surveyor	1.50%	37,610		45,768	
Building Services Structural Consolidating Brief Feasibility Stage 1A Site Model	6.00% 5.00%	20,229 46,162		38,469 37,501	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 32	5000 12,537 8,800		5000 15,256 8,800	
			376,123		432,155
28-59 Wolverton	TOTAL £		2,883,450		3,483,382

	Î	Decent Homes		Decent Ho	omes +
60-84 Wolverton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 0 69,507 0 0 18,962 89,310 131,712 10,528 137,359 102,775 0 1,189 236,448 85,576 90,218		0 0 0 0 69,507 0 18,962 89,310 131,712 10,528 137,359 102,775 0 1,189 236,448 85,576 90,218	
IMPROVEMENT WORKS TOTAL £		973,582	973,582	973,582	973,582
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		57,868 67,883 9,086 0 24,674 7,274 16,213		0 67,883 9,086 0 24,674 7,274 16,213	
PPM WORKS TOTAL £		182,996	182,996	125,128	125,128
SUB-TOTAL £	(10.11.11.11	1,156,578		1,098,709	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(10 Units)	309,700 see mech services 20,967 43,546 42,384 15,823	309,700	201,432 see mech services 20,967 43,546 42,384 15,823	201,432
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				112,500 75,000 112,500 237,500	
DECENT HOMES TOTAL £		122,719	122,719	660,219	660,219
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		7,415 285,013 0	292,428	7,415 365,638 0	373,053
TOTAL £		1,881,424		2,333,413	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	18,438 12,960 7,700 19,250 2,310		22,867 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Bigs Only)		1,739		2,159	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	5,254 4,704		6,524 5,834	
Architect Quantity Surveyor	5.00% 1.50%	94,071 28,221		116,671 35,001	
Building Services Structural	6.00% 5.00%	15,804 32,193		30,054 26,780	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 25	5000 9,407 6,875		5000 11,667 6,875	
60-84 Wolverton	TOTAL £	_	301,926 2,183,350	_	349,651 2,683,065

		Decent Home	es	Decent Ho	omes +
85-104 Wolverton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 0 82,220 50,862 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 105,369 8,422 0 82,220 50,862 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		719,840	719,840	719,840	719,840
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		46,295 54,306 7,268 0 19,739 5,819 12,970		0 54,306 7,268 0 19,739 5,819 12,970	
PPM WORKS TOTAL £		146,397	146,397	100,102	100,102
SUB-TOTAL £		866,237		819,942	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 see mech services 16,774 34,836 33,907 12,659	0	0 see mech services 16,774 34,836 33,907 12,659	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,932 228,010 0 1,196,354	233,942	5,932 292,510 0 1,646,560	298,442
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	11,744 12,960 7,700 19,250 2,310		16,136 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,151 3,476		1,571 4,746	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	2,996 59,918 17,975		4,116 82,328 24,698	
Building Services Structural	6.00% 5.00%	12,643 13,367		24,043 13,367	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 5,992 5,500		5000 8,233 5,500	
85-104 Wolverton	TOTAL £		219,981	-	269,958 1,916,518
00-104 WOONGILOII	TOTAL &	1	1,410,333		1,910,018

		Decent Homes		Decent Ho	mes +
105-125 Wolverton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 58,386 0 0 15,928 75,020 110,638 8,43 115,381 86,331 0 999 198,616 71,884 75,783		0 0 0 0 58,386 0 0 15,928 75,020 110,638 8,843 115,381 86,331 0 999 198,616 71,884 75,783	
IMPROVEMENT WORKS TOTAL £		817,809	817,809	817,809	817,809
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings PPM WORKS TOTAL £		48,609 57,021 7,632 0 20,726 6,110 13,619	153.716	0 57,021 7,632 0 20,726 6,110 13,619	105.107
FFINI WORKS TOTAL I		100,710	155,716	100,107	103,107
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(9 Units)	971,525 278,730	278,730	922,916 181,289	181,289
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(9 Offits)	see mech services 17,612 36,578 35,602 13,292	2/8,/30	see mech services 17,612 36,578 35,602 13,292	101,209
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				94,500 63,000 94,500 199,500	
DECENT HOMES TOTAL £		103,084	103,084	554,584	554,584
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		6,228 239,411 0 1,598,978	245,639	6,228 307,136 0 1,972,153	313,364
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	15,670 12,960 7,700 19,250 2,310		19,327 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,487 4,492		1,823 5,508	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	3,997 79,949 23,985		4,930 98,608 29,582	
Building Services Structural	6.00% 5.00%	13,275 27,971		25,245 23,099	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 21	5000 7,995 5,775		5000 9,861 5,775	
105-125 Wolverton	TOTAL £		269,816 1,868,795	_	308,979 2,281,132

126-151 Wolverton		I	Decent Hom	es	Decent Ho	imes +
Reducta/ment of Sartower	126-151 Wolverton		3000 K 1 0 11	00	Decement	illes i
PPM WORKS NC DECENT HOMES EXTERNALS	Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 72,287 0 0 19,720 92,882 136,980 10,949 142,853 106,886 0 1,236 245,906 88,999		0 0 0 72,287 0 0 19,720 92,882 136,980 10,949 142,853 106,886 0 1,236 245,906 88,999	
Mindow Repairs   Fooding   Position   Posi	IMPROVEMENT WORKS TOTAL £		1,012,525	1,012,525	1,012,525	1,012,525
SUB-TOTAL E   1,202,841   1,142,658   282,005   28	Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		70,598 9,449 0 25,660 7,564 16,861		70,598 9,449 0 25,660 7,564 16,861	
STRUCTURAL STRENGTHENING WORKS	PPM WORKS TOTAL £		190,316	190,316	130,133	130,133
DECENT HOMES INTERNALS						
Extract Ventilation to Dwellings   Some mech services   Some Mechanical Services to Dwellings   Replacement Electrical Works to Dwellings   Asbestos Removal		(14 Units)	433,580	433,580	282,005	282,005
Works to Ritchens         117,000           Works to Bathrooms         78,000           Window Replacement         127,628         127,628         686,628         68           CHP Works         127,628         127,628         686,628         68           DAYWORKS & PRELIMINARIES         Dayworks         7,711         7,711         7,711           Provisional Work / Items (inc main contingency)         296,414         380,264         380,264           Preliminaries is sterowing in the provisional Work / Items (inc main contingency)         0         304,125         0         38           TOTAL £         2.068,173         2.499,265         \$	Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings		21,806 45,287 44,079		21,806 45,287 44,079	
DAYWORKS & PRELIMINARIES   Dayworks   Provisional Work / Items (inc main contingency)   Main Preliminaries   296.414   380,264   0 304,125   0 38	Works to Kitchens Works to Bathrooms Window Replacement				78,000 117,000	
1,711	DECENT HOMES TOTAL £		127,628	127,628	686,628	686,628
SBDS Staff SW Corner   0.98%   20,268   24,493   SBDS Staff SW Corner Additional Services   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   12,960   19,250	Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		296,414 0	304,125	380,264 0	387,975
NCD Consultation & Communication         1,907         2,243           Building Control Inspection (Blgs Only)         5,762         6,778           Lead Design Fees         0.25%         5,170         6,248           Architect         5,00%         103,409         124,963           Quantity Surveyor         1,50%         31,023         37,489           Building Services         6,00%         16,436         31,256           Structural         5,00%         39,055         31,477           Consolidating Brief         Feasibility Stage 1A         31,477           Site Based Engineer         10000         10000           Site Based Architect         20000         20000           Site Based Clerk of Works         5000         5000           Site Based Quantity Surveyor         3000         5000           Incidental Expenses & Disbursements         5000         5000           Planning Supervisor         0.50%         10,341         12,496	SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management	2004-2005	12,960 7,700 19,250		12,960 7,700 19,250	
Building Control Inspection (Blgs Only)  Lead Design Fees 0.25% 5.170 6.248 Architect 5.00% 103,409 124,963 Quantity Surveyor 1.50% 31,023 37,489  Building Services 6.00% 16,436 31,256 Structural 5.00% 39,055 31,477  Consolidating Brief Feasibility Stage 1A Site Model  Site Based Engineer 10000 10000 Site Based Architect 20000 20000 Site Based Architect 5000 5000 Site Based Quantity Surveyor 30000 Incidental Expenses & Disbursements 10,341 12,496						
Architect 5.00% 103,409 124,963 37,489	Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)					
Structural	Architect	5.00%	103,409		124,963	
Feasibility Stage 1A         Site Model           Site Based Engineer         10000         10000           Site Based Architect         20000         20000           Site Based Clerk of Works         5000         5000           Site Based Quantity Surveyor         3000         3000           Incidental Expenses & Disbursements         5000         5000           Planning Supervisor         0.50%         10,341         12,496						
Site Based Architect         20000         20000           Site Based Clerk of Works         5000         5000           Site Based Quantity Surveyor         3000         3000           Incidental Expenses & Disbursements         5000         5000           Planning Supervisor         0.50%         10,341         12,496	Feasibility Stage 1A					
Planning Supervisor 0.50% 10,341 12,496	Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		20000 5000 3000		20000 5000 3000	
	Planning Supervisor		10,341		12,496	
	126-151 Wolverton	TOTAL £	_	•	_	369,813 2,869,079

PPM WORKS INC. DECENT HOMES EXTERNALS         0         0         0         0         65,167         65,167         65,167         65,167         65,167         0 <th></th> <th></th> <th>Decent He</th> <th>omes</th> <th>Decent H</th> <th>omes +</th>			Decent He	omes	Decent H	omes +
Reductionment of Santowner   0   0   0   0   0   0   0   0   0	152-175 Wolverton					
MPROVEMENT WORKS TOTAL £   934.638	Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Gencosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)		0 0 0 66,727 0 0 18,203 85,737 126,443 10,107 131,864 98,664 0 1,1,41 226,990 82,153		0 0 0 66,727 0 18,203 85,737 126,443 10,107 131,864 98,664 0 1,141 226,990 82,153	
Mindow Repairs   55,554   0   0     Roofing Drainage   5,167   6,167	IMPROVEMENT WORKS TOTAL £		934,638	934,638	934,638	934,638
SUB-TOTAL E	Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		65,167 8,722 0 23,687 6,983 15,564		65,167 8,722 0 23,687 6,983 15,564	
STRUCTURAL STRENGTHENING WORKS   0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	PPM WORKS TOTAL £		1/5,6/6	175,676	120,122	120,122
DECENT HOMES INTERNALS						
Works to Ritchens         108,000           Works to Bathrooms         172,000           Window Replacement         108,000           CHP Works         117,810         117,810           DECENT HOMES TOTAL £         117,810         117,810         633,810         63           DAYWORKS & PRELIMINARIES         Dayworks         7,118	DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings		see mech services 20,128 41,804 40,688	0	see mech services 20,128 41,804 40,688	0
DAYWORKS & PRELIMINARIES   Dayworks   Provisional Work / Items (inc main contingency)   Main Preliminaries   273,612   351,012   0 280,730   0 35   1,508,855   2,046,702	Works to Kitchens Works to Bathrooms Window Replacement				72,000 108,000	
Dayworks	DECENT HOMES TOTAL £		117,810	117,810	633,810	633,810
FEES   SBDS Staff SW Corner   0.98%   14,787   20,058   SBDS Staff SW Corner Additional Services   12,960   12,960   12,960   12,960   SBDS Staff SW Corner Additional Services   5,700   7,700   7,700   5,700   7,700   5,700   19,250	Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		273,612 0	280,730	351,012 0	358,130
Planning Fees (Blgs Only)	SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	2004-2005	12,960 7,700 19,250		12,960 7,700 19,250	
Lead Design Fees     0.25% Architect     3,772 5,443     5,117 102,335       Quantity Surveyor     1.50% 22,633     30,701       Building Services     6.00% 5tructural     15,172 2 28,852 16,040     28,852 16,040       Consolidating Brief Feasibility Stage 1A Site Model     10000 10000 10000 20000 20000 20000 5000 5	Planning Fees (Blgs Only)					
Structural	Lead Design Fees Architect	5.00%	3,772 75,443		5,117 102,335	
Feasibility Stage 1A   Site Model   Site Based Engineer   10000   10000   20000   20000   20000   Site Based Architect   20000   5000   5000   5000   Site Based Clerk of Works   5000   5000   3000   Site Based Quantity Surveyor   3000   3000   3000   Site Based Quantity Surveyor   5000   5000   5000   Flanning Supervisor   5000   7,544   10,234   5000   5	Structural					
Site Based Architect         20000         20000           Site Based Clerk of Works         5000         5000           Site Based Quantity Surveyor         3000         3000           Incidental Expenses & Disbursements         5000         5000           Planning Supervisor         0.50%         7,544         10,234	Feasibility Stage 1A					
Planning Supervisor 0.50% 7,544 10,234	Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		20000 5000 3000		20000 5000 3000	
	Planning Supervisor		7,544		10,234	
	152-175 Wolverton	TOTAL £	_		-	312,824 2,359,526

	ĺ	Decent Homes		Decent H	omes +
176-192 Wolverton					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 47,265 0 0 12,894 60,730 89,564 7,159 0 69,887 43,233 808 160,785 58,192 61,348		0 0 0 47,265 0 12,894 60,730 89,564 7,159 0 69,887 42,233 8088 160,785 58,192 61,348	
IMPROVEMENT WORKS TOTAL £		611,864	611,864	611,864	611,864
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		39,350 46,160 6,178 0 16,778 4,946 11,025		0 46,160 6,178 0 16,778 4,946 11,025	
PPM WORKS TOTAL £		124,437	124,437	85,087	85,087
SUB-TOTAL £		736,301		696,951	
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS		0	0	0	0
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 14,258 29,611 28,821 10,760		see mech services 14,258 29,611 28,821 10,760	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				76,500 51,000 76,500 161,500	
DECENT HOMES TOTAL £		83,449	83,449	448,949	448,949
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,042 193,809 0 1,018,601	198,851	5,042 248,634 0 1,399,576	253,676
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	9,982 12,960 7,700 19,250 2,310		13,716 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,067 3,222		1,319 3,984	
Lead Design Fees Architect	0.25% 5.00%	2,547 50,930		3,499 69,979	
Quantity Surveyor  Building Services	1.50% 6.00%	15,279 10,747		20,994 20,437	
Structural  Consolidating Brief  Feasibility Stage 1A  Site Model	5.00%	11,362		11,362	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 17	5000 5,093 4,675		5000 6,998 4,675	
176-192 Wolverton	TOTAL £		200,123	_	242,181 1,641,757
170-132 VVOIVEILUII	TOTAL		1,210,724		1,041,737

		Decent Ho	mes	Decent H	omes +
1-30 Soane House					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BMIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 83,408 0 0 22,754 107,171 158,054 12,633 0 123,330 0 1,427 283,738 102,691 108,261		0 0 0 0 0 0 22,754 107,171 158,054 12,633 0 123,330 0 1,427 283,738 102,691	
IMPROVEMENT WORKS TOTAL £		1,003,468	1,003,468	1,003,468	1,003,468
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		69,442 81,459 10,903 0 29,608 8,728 19,455		0 81,459 10,903 0 29,608 8,728 19,455	
PPM WORKS TOTAL £		219,595	219,595	150,153	150,153
SUB-TOTAL £		1,223,063		1,153,621	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 25,160 52,255 50,860 18,988		see mech services 25,160 52,255 50,860 18,988	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				135,000 90,000 135,000 285,000	
DECENT HOMES TOTAL £		147,263	147,263	792,263	792,263
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		8,897 342,016 0 1,721,239	350,913	8,897 438,766 0 2,393,547	447,663
FEES		1,721,239		2,393,347	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	16,868 12,960 7,700 19,250 2,310		23,457 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		1,655		2,159	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	5,000 4,303		6,524 5,984	
Architect Quantity Surveyor	5.00% 1.50%	86,062 25,819		119,677 35,903	
Building Services Structural	6.00% 5.00%	18,965 20,050		36,065 20,050	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 30	5000 8,606 8,250		5000 11,968 8,250	
1.20 Spana Usivas	TOTAL	_	280,797	_	355,256
1-30 Soane House	TOTAL £		2,002,036		2,748,803

	I	Decent Homes		Decent Homes +
31-35 Soane House				
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 13,901 0 0 3,792 17,862 26,342 2,106 0 20,555 12,716 238 47,290 17,115 18,044		0 0 0 0 13,901 0 0 3,792 17,862 26,342 2,106 0 20,555 12,716 238 47,290 17,115 18,044
IMPROVEMENT WORKS TOTAL £		179,960 1	79,960	179,960 179,960
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		11,574 13,577 1,817 0 4,935 1,455 3,243		0 13,577 1,817 0 4,935 1,455 3,243
PPM WORKS TOTAL £		36,599	36,599	25,026 25,026
SUB-TOTAL £		216,559		204,986
STRUCTURAL STRENGTHENING WORKS		0	0	0 0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 4,193 8,709 8,477 3,165		0 4,193 8,709 8,477 3,165
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				22,500 15,000 22,500 47,500
DECENT HOMES TOTAL £		24,544	24,544	132,044 132,044
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		1,483 57,003 0 299,589	58,486	1,483 73,128 0 74,611 411,640
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	2,936 12,960 7,700 19,250 2,310		4,034 12,960 7,700 19,250 2,310
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		563 1,698		563 1,698
Lead Design Fees	0.25%	749		1,029
Architect Quantity Surveyor	5.00% 1.50%	14,979 4,494		20,582 6,175
Building Services Structural	6.00% 5.00%	3,161 3,342		6,011 3,342
Consolidating Brief Feasibility Stage 1A Site Model				
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 5	5000 1,498 1,375		5000 2,058 1,375
			20,014	132,086
31-35 Soane House	TOTAL £	4	19,603	543,726

		Decent Homes		Decent Home	es +
1-12 Lees					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demollition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 33,363 0 0 9,102 42,869 63,222 5,053 0 49,332 0 571 113,495 41,076 43,304		0 0 0 0 33,363 0 0 9,102 42,869 63,222 5,053 0 49,332 0 571 113,495 41,076 43,304	
IMPROVEMENT WORKS TOTAL £		401,387	401,387	401,387	401,387
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		27,777 32,584 4,361 0 11,843 3,491 7,782		0 32,584 4,361 0 11,843 3,491 7,782	
PPM WORKS TOTAL £		87,838	87,838	60,061	60,061
SUB-TOTAL £		489,225		461,448	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 10,064 20,902 20,344 7,595		0 10,064 20,902 20,344 7,595	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				54,000 36,000 54,000 114,000	
DECENT HOMES TOTAL £		58,905	58,905	316,905	316,905
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		3,559 136,806 0	140,365	3,559 175,506 0	179,065
TOTAL £ FEES		688,495		957,419	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management	0.98% 2004-2005 2005-2008	6,747 12,960 7,700 19,250 2,310		9,383 12,960 7,700 19,250 2,310	
NCD Consultation & Communication		701		002	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		731 2,206		983 2,968	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	1,721 34,425 10,327		2,394 47,871 14,361	
Building Services Structural	6.00% 5.00%	7,586 8,020		14,426 8,020	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 12	5000 3,442 3,300		5000 4,787 3,300	
1-12 Lees	TOTAL £		163,726 852,221		193,712 1,151,131

		Decent Homes		Decent Homes +
1-43 Missenden				
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mcchanical & Electrical (prov sums/contingency)		0 0 0 0 0 119,552 0 0 32,614 153,612 226,544 18,108 445,042 176,773 0 2,045 766,092 277,266 155,174		0 0 0 0 119,552 0 0 32,614 153,612 226,544 18,108 445,042 176,773 0 2,045 766,092 277,266 155,174
IMPROVEMENT WORKS TOTAL £		2,372,822	2,372,822	2,372,822 2,372,822
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		99,533 116,758 15,627 0 42,438 12,510 27,886		0 116,758 15,627 0 42,438 12,510 27,886
PPM WORKS TOTAL £		314,753	314,753	215,219 215,219
SUB-TOTAL £		2,687,575		2,588,042
STRUCTURAL STRENGTHENING WORKS	(17 Units)	526,490	526,490	342,435 342,435
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		0 36,063 74,898 72,900 27,216		0 36,063 74,898 72,900 27,216
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				193,500 129,000 193,500 408,500
DECENT HOMES TOTAL £		211,077	211,077	1,135,577 1,135,577
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		12,753 490,222 0	502,975	12,753 628,897 0 641,650
TOTAL £		3,928,117		4,707,704
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management	0.98% 2004-2005 2005-2008	38,496 12,960 7,700 19,250 2,310		46,135 12,960 7,700 19,250 2,310
NCD Consultation & Communication  Planning Fees (Blgs Only)		3,503		4,175
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	10,588 9,820		12,620 11,769
Architect Quantity Surveyor	5.00% 1.50%	196,406 58,922		235,385 70,616
Building Services Structural	6.00% 5.00%	34,988 55,063		59,498 45,860
Consolidating Brief Feasibility Stage 1A Site Model				
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 43	5000 19,641 11,825		5000 23,539 11,825
1-43 Missenden	TOTAL £		524,470 4,452,587	606,641 5,314,345

44-75 Missenden  IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)	0 0 0 0 0 0 88,969 0 0 24,271 114,316 168,591 13,476 175,819 131,552 0 1,522 302,653 109,537 115,478		Decent Hom  0 0 0 0 88,969 0 0 24,271 114,316 168,591 13,476 175,819 131,552	
Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries)	0 0 0 0 88,969 0 0 24,271 114,316 168,591 13,476 175,819 131,552 0 1,522 302,653 109,537 115,478		0 0 88,969 0 0 24,271 114,316 168,591 13,476 175,819 131,552	
	1 246 185		1,522 302,653 109,537 115,478	
IMPROVEMENT WORKS TOTAL £	1,240,100	1,246,185	1,246,185	1,246,185
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings	74,071 86,890 11,629 0 31,582 9,310 20,752		0 86,890 11,629 0 31,582 9,310 20,752	
PPM WORKS TOTAL £	234,235	234,235	160,163	160,163
SUB-TOTAL £	1,480,419		1,406,348	
STRUCTURAL STRENGTHENING WORKS (15 Units)  DECENT HOMES INTERNALS	464,550	464,550	302,148	302,148
Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	see mech services 26,838 55,738 54,251 20,254		see mech services 26,838 55,738 54,251 20,254	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works			144,000 96,000 144,000 304,000	
DECENT HOMES TOTAL £	157,081	157,081	845,081	845,081
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £	9,491 364,817 0 2,476,357	374,307	9,491 468,017 0 3,031,084	477,507
FEES SBDS Staff SW Corner 0.98% SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management 2004-2005 SBDS Staff Programme Management 2005-2008  NCD Staff NCD Consultation & Communication	24,268 12,960 7,700 19,250 2,310		29,705 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)	2,243 6,778		2,747 8,302	
Lead Design Fees         0.25%           Architect         5.00%           Quantity Surveyor         1.50%	6,191 123,818 37,145		7,578 151,554 45,466	
Building Services 6.00% Structural 5.00%	20,229 44,614		38,469 36,494	
Consolidating Brief Feasibility Stage 1A Site Model	7,,5		35,16.	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor	10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor 0.50% Condition / Measured Surveys? / Site Prep 32	5000 12,382 8,800		5000 15,155 8,800	
		371,688		429,490
44-75 Missenden TOTAL £	<u> </u>	2,848,045		3,460,574

		Decent Homes		Decent Ho	omes +
256-299 Missenden					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas:Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 122,332 0 0 33,372 157,185 94,832 18,529 241,751 180,884 0 2,092 416,148 150,614		0 0 0 0 122,332 0 0 33,372 157,185 94,832 18,529 241,751 180,884 0 2,092 416,148 150,614 158,783	
IMPROVEMENT WORKS TOTAL £		1,576,524	1,576,524	1,576,524	1,576,524
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		101,848 119,473 15,990 0 43,425 12,801 28,534	200 070	0 119,473 15,990 0 43,425 12,801 28,534	200.004
PPM WORKS TOTAL £		322,073	322,073	220,224	220,224
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS	(21 Units)	1,898,596 650,370	650.370	1,796,748 423,008	423,008
DECENT HOMES INTERNALS  Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(21 Offits)	see mech services 36,902 76,640 74,595 27,849	650,370	423,008 see mech services 36,902 76,640 74,595 27,849	423,008
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				198,000 132,000 198,000 418,000	
DECENT HOMES TOTAL £		215,986	215,986	1,161,986	1,161,986
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		13,050 501,623 0 3,279,624	514,672	13,050 643,523 0 4,038,314	656,572
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	32,140 12,960 7,700 19,250 2,310		39,575 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		2,915 8,810		3,587 10,842	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	8,199 163,981 49,194		10,096 201,916 60,575	
Building Services Structural Consolidating Brief	6.00% 5.00%	27,815 55,076		52,895 43,708	
Feasibility Stage 1A Site Model Site Based Engineer		10000		10000	
Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		20000 5000 3000		20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 44	5000 16,398 12,100		5000 20,192 12,100	
255 200 Missandan	TOTAL		461,849	_	540,705
256-299 Missenden	TOTAL £		3,741,473	I	4,579,019

		Decent Homes		Decent Ho	omes +
300-313 Missenden					
IMPROVEMENT WORKS  Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 38,924 0 0 10,618 50,013 342,451 5,896 76,921 57,554 666 132,411 47,923 50,522		0 0 0 0 38,924 0 0 10,618 50,013 342,451 5,896 76,921 57,554 0 666 132,411 47,923 50,522	
IMPROVEMENT WORKS TOTAL £		813,898	813,898	813,898	813,898
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofling Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		32,406 38,014 5,088 0 13,817 4,073 9,079	102.478	0 38,014 5,088 0 13,817 4,073 9,079	70074
PPM WORKS TOTAL £		102,476	102,478	70,071	70,071
SUB-TOTAL £	(6 Units)	916,375	105 000	883,969	100.050
STRUCTURAL STRENGTHENING WORKS  DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings	(6 Units)	185,820 see mech services 11,742 24,385 23,735 8,861	185,820	120,859 see mech services 11,742 24,385 23,735 8,861	120,859
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				63,000 42,000 63,000 133,000	
DECENT HOMES TOTAL £		68,723	68,723	369,723	369,723
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		4,152 159,607 0 1,334,678	163,759	4,152 204,757 0 1,583,461	208,909
FEES		1,334,076		1,363,461	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	13,080 12,960 7,700 19,250 2,310		15,518 12,960 7,700 19,250 2,310	
Planning Fees (Blgs Only)		1,319		1,487	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	3,984 3,337		4,492 3,959	
Architect Quantity Surveyor	5.00% 1.50%	66,734 20,020		79,173 23,752	
Building Services Structural	6.00% 5.00%	8,850 32,082		16,830 28,834	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 14	5000 6,673 3,850		5000 7,917 3,850	
300-313 Missenden	TOTAL £		245,149 1,579,827	_	271,032 1,854,493
OU OTO IVIIGOCITACIT	TOTAL	1	.,070,027	ľ	1,004,400

	ĺ	Decent Hor	mes	Decent H	omes +
1-36 Michael Faraday					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BMIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 100,090 0 27,305 128,606 94,832 15,160 0 147,996 91,552 1,712 340,485 123,229 129,913		0 0 0 100,090 0 27,305 128,606 94,832 15,160 0 147,996 91,552 1,712 340,485 123,229	
IMPROVEMENT WORKS TOTAL £		1,200,880	1,200,880	1,200,880	1,200,880
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		83,330 97,751 13,083 0 35,530 10,474 23,346		97.751 13,083 0 35,530 10,474 23,346	
PPM WORKS TOTAL £		263,514	263,514	180,184	180,184
SUB-TOTAL £		1,464,394		1,381,064	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 30,192 62,706 61,032 22,785		see mech services 30,192 62,706 61,032 22,785	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				162,000 108,000 162,000 342,000	
DECENT HOMES TOTAL £		176,716	176,716	950,716	950,716
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		10,677 410,419 0	421,096	10,677 526,519 0	537,196
TOTAL £		2,062,205		2,868,975	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff	0.98% 2004-2005 2005-2008	20,210 12,960 7,700 19,250 2,310		28,116 12,960 7,700 19,250 2,310	
NCD Consultation & Communication  Planning Fees (Bigs Only)		1,907		2,579	
Building Control Inspection (Blgs Only)  Lead Design Fees	0.25%	5,762 5,156		7,794 7,172	
Architect Quantity Surveyor	5.00% 1.50%	103,110 30,933		143,449 43,035	
Building Services Structural	6.00% 5.00%	22,758 19,318		43,278 19,318	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 36	5000 10,311 9,900		5000 14,345 9,900	
1-36 Michael Faradav	TOTAL £	_	314,584 2,376,790	-	404,205 3,273,181

		Decent Ho	omes	Decent H	omes +
37-56 Michael Faraday					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 105,369 8,422 0 82,220 50,862 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 105,369 8,422 0 82,220 50,862 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		719,840	719,840	719,840	719,840
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings		46,295 54,306 7,268 0 19,739 5,819 12,970		0 54,306 7.268 0 19,739 5,819 12,970	
PPM WORKS TOTAL £		146,397	146,397	100,102	100,102
SUB-TOTAL £		866,237		819,942	
STRUCTURAL STRENGTHENING WORKS		0	0	0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,774 34,836 33,907 12,659		see mech services 16,774 34,836 33,907 12,659	
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums		5,932 228,010 0	233,942	5,932 292,510 0	298,442
TOTAL £		1,198,354		1,646,560	
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	11,744 12,960 7,700 19,250 2,310		16,136 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,151		1,571 4,746	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	3,476 2,996 59,918 17,975		4,116 82,328 24,698	
Building Services Structural	6.00% 5.00%	12,643 13,367		24,043 13,367	
Consolidating Brief Feasibility Stage 1A Site Model	3.00 /6	10,007		10,007	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 5,992 5,500		5000 8,233 5,500	
37-56 Michael Faraday	TOTAL £	_	219,981 1,418,335	-	269,958 1,916,518

		Decent Homes		Decent Ho	omes +
57-76 Michael Faraday					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		0 0 0 0 55,606 0 0 15,169 71,448 163,323 8,422 0 82,220 50,862 951 189,158 68,461 72,174		0 0 0 0 55,606 0 15,169 71,448 163,323 8,422 0 82,220 50,862 951 189,158 68,461 72,174	
IMPROVEMENT WORKS TOTAL £		777,794	777,794	777,794	777,794
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs Works to Cold Water Tanks Front Doors to Dwellings  PPM WORKS TOTAL £		46,295 54,306 7,268 0 19,739 5,819 12,970	146,397	0 54,306 7,268 0 19,739 5,819 12,970	100,102
PPM WORKS TOTAL 2		140,007	146,397	100,102	100,102
SUB-TOTAL £ STRUCTURAL STRENGTHENING WORKS		924,190 0	0	877,896 0	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings BWIC with services to Dwellings		see mech services 16,774 34,836 33,907 12,659	0	see mech services 16,774 34,836 33,907 12,659	0
DECENT HOMES + Works to Kitchens Works to Bathrooms Window Replacement CHP Works				90,000 60,000 90,000 190,000	
DECENT HOMES TOTAL £		98,175	98,175	528,175	528,175
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency) Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		5,932 228,010 0 1,256,308	233,942	5,932 292,510 0 1,704,513	298,442
FEES SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management NCD Staff NCD Consultation & Communication	0.98% 2004-2005 2005-2008	12,312 12,960 7,700 19,250 2,310		16,704 12,960 7,700 19,250 2,310	
Planning Fees (Bigs Only) Building Control Inspection (Bigs Only)		1,235 3,730		1,655 5,000	
Lead Design Fees Architect	0.25% 5.00%	3,141 62,815		4,261 85,226	
Quantity Surveyor  Building Services	1.50% 6.00%	18,845 12,643		25,568 24,043	
Structural  Consolidating Brief  Feasibility Stage 1A  Site Model	5.00%	16,264		16,264	
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 20	5000 6,282 5,500		5000 8,523 5,500	
57-76 Michael Faraday	TOTAL £		227,986	_	277,964 1,982,477
-	_	1		1	,

		Decent Home	es	Decent H	omes +
77-105 Michael Faraday					
IMPROVEMENT WORKS Refurbishment of Stairtower 1 Refurbishment of Stairtower 2 Refurbishment of Stairtower 3 Refurbishment of Enclosed Access Corridors Refurbishment Common Areas/Walkways Screens to Stairtowers & Common Areas		0 0 0 0 80,628 0		0 0 0 0 0 80,628	
Screens and Gabion Walls to Offices Infill dwellings Demolition of Walkways, Bridges & Ramps New Stair and Lift Cores External Walls Conversion of Garages to Entrance Halls		0 21,995 103,599 163,323 12,212 0		0 21,995 103,599 163,323 12,212 0	
Access Alterations to Upper Level Dwellings Entrance Porches to Dwellings BWIC With External Mains External Works Mechanical & Electrical Services (inc preliminaries) Mechanical & Electrical (prov sums/contingency)		119,219 73,750 1,379 274,280 99,268 104,652		119,219 73,750 1,379 274,280 99,268 104,652	
IMPROVEMENT WORKS TOTAL £		1,054,306	1,054,306	1,054,306	1,054,306
PPM WORKS INC. DECENT HOMES EXTERNALS Window Repairs Roofing Drainage Tank Rooms Concrete Repairs		67,127 78,744 10,539 0 28,621 8,437		0 78,744 10,539 0 28,621 8,437	
Works to Cold Water Tanks Front Doors to Dwellings		18,807	242.275	18,807	445.440
PPM WORKS TOTAL £		212,275	212,275	145,148	145,148
SUB-TOTAL £  STRUCTURAL STRENGTHENING WORKS		1,266,581	0	1,199,453	0
DECENT HOMES INTERNALS Extract Ventilation to Dwellings Overhaul Mechanical Services to Dwellings Replacement Electrical Works to Dwellings Asbestos Removal to Dwellings		see mech services 24,322 50,513 49,165		see mech services 24,322 50,513 49,165	
BWIC with services to Dwellings  DECENT HOMES + Works to Kitchens		18,355		18,355 130,500	
Works to Bathrooms Window Replacement CHP Works				87,000 130,500 275,500	
DECENT HOMES TOTAL £		142,354	142,354	765,854	765,854
DAYWORKS & PRELIMINARIES Dayworks Provisional Work / Items (inc main contingency)		8,601		8,601	
Main Preliminaries Preliminaries/Site overheads on defined Prov Sums TOTAL £		330,615 0 1,748,151	339,216	424,140 0 2,398,049	432,741
FEES		1,740,151		2,390,049	
SBDS Staff SW Corner SBDS Staff SW Corner Monitoring SBDS Staff SW Corner Additional Services SBDS Staff Programme Management SBDS Staff Programme Management	0.98% 2004-2005 2005-2008	17,132 12,960 7,700 19,250 2,310		23,501 12,960 7,700 19,250 2,310	
NCD Staff NCD Consultation & Communication					
Planning Fees (Blgs Only) Building Control Inspection (Blgs Only)		1,655 5,000		2,159 6,524	
Lead Design Fees Architect Quantity Surveyor	0.25% 5.00% 1.50%	4,370 87,408 26,222		5,995 119,902 35,971	
Building Services Structural	6.00% 5.00%	18,333 19,908		34,863 19,908	
Consolidating Brief Feasibility Stage 1A Site Model					
Site Based Engineer Site Based Architect Site Based Clerk of Works Site Based Quantity Surveyor		10000 20000 5000 3000		10000 20000 5000 3000	
Incidental Expenses & Disbursements Planning Supervisor Condition / Measured Surveys? / Site Prep	0.50% 29	5000 8,741 7,975		5000 11,990 7,975	
			281,964		354,008
77-105 Michael Faraday Total Estimated Cost at 1st Quarter 2005 g	TOTAL £		2,030,114 191,326,106	-	2,752,057 255,810,499
Total Estimated Cost at 1st Quarter 2005 p	nices		191,326,106		255,810,499